Planning and Zoning Commission
Hearing Date: May 21, 2026
Canyon County Development Services Department

PLANNING DIVISION STAFF REPORT

CASE NUMBER: **CU2025-0031**

APPLICANT/PROPERTY OWNER: **Lucus Hansen**

APPLICATION: **Conditional Use Permit – Slaughterhouse**

LOCATION: **0 Hwy 95, Parma**
R39357012

PLANNER: **Amber Lewter, Associate Planner**

STAFF RECOMMENDATION: **Approval**

REQUEST:
The applicant, Lucas Hansen, is requesting a Conditional Use Permit for a Slaughterhouse on approximately 11.30 acres in the "A" (Agricultural) zone. The request is for a custom slaughterhouse in which the applicant will accept animals from customers for processing. The request includes retail sales of the processed meat as an accessory use to the slaughterhouse. Proposed hours of operation for the slaughterhouse and the retail sales are Monday – Saturday, 7 am to 5 pm.

PARCEL INFORMATION REPORT: *See **Exhibit C.1** for information*

APPLICABLE CODE:
The following laws and ordinances apply to this decision: Canyon County Code of Ordinances (CCCO) §01-17 (Land Use/Land Division Hearing Procedures), CCCO §07-05 (Notice, Hearing and Appeal Procedures), CCCO §07-07 (Conditional Use Permits), CCCO §07-02-03 (Definitions), CCCO §07-10-27 (Land Use Regulations (Matrix)), CCCO §07-14 (Use Standards), and Idaho Code §67-6512 (Special Use Permits, Conditions, and Procedures).

BACKGROUND:
Parcel R39357012 was created by an approved land division and building permit transfer on June 18, 2020 (AD2019-0166).

There appears to be an agriculture (AG) building on site that has expired and has received no inspections. If the applicant plans to use the structure for the slaughterhouse, a commercial change of occupancy will be required, otherwise the structure will need to be permitted as an agriculture (AG) building (**Exhibit E7**). *See condition number 2a.*

The subject parcel contains slopes over 15% per the USGS Slope Map (**Exhibit C2.14**). Development on slopes 15% or greater requires an engineered drainage and grading plan per CCCO §07-17-33(1)C. *See condition number 2b.*

HEARING CRITERIA:

Table 1. Conditional Use Permit Standards of Evaluation Analysis

Standards of Evaluation – CCCO §07-07-05: The presiding party shall consider each conditional use permit application by finding adequate evidence to answer the following questions in its FCOs:		
County Ordinance and Review		
Criteria Met?	**Code Section**	**Criteria**
Yes	**1**	**Is the proposed use permitted in the zone by conditional use permit?**
Analysis	The proposed use for a slaughterhouse is permitted in the zone by a conditional use permit, pursuant to CCCO §07-10-27. The applicant submitted a conditional use permit for a slaughterhouse on November 10, 2025. *See **Exhibit A** for the application and submitted materials.* • CCCO §07-02-03 defines a slaughterhouse as "*A facility where animals are killed and may be processed into meat products.*" See project description analysis contained in Section 07-07-05(2) detailing the nature of the request.	
Criteria Met? **Yes**	**2**	**What is the nature of the request?**
Analysis	The property owner, Lucus Hansen, requests a conditional use permit to establish a slaughterhouse on an approximately 11.30-acre parcel in the "A" (Agricultural) zone, designated as parcel R39357012. • Use: The nature of the request consists of using the subject property to conduct the applicant's slaughterhouse business. The applicant anticipates slaughtering approximately 10 animals per week; the animals will be mostly beef and pigs. The proposed building is 60 feet by 100 feet. Located behind the proposed building is a pasture and a holding pen. The facility will include a restroom, a breakroom, and a retail store selling the processed meat as an accessory to the slaughterhouse (**Exhibits B2, B2.1, B2.2, and B3**). • Number of Employees: The applicant is proposing to have a maximum of eight (8) employees. (**Exhibit B4**). • Hours of Operation: The hours of operation proposed are Monday through Saturday from 7 am to 5 pm (**Exhibit B4**). • Parking: According to email correspondence and the land use matrix, the applicant is proposing five to six (5 to 6) paved parking spaces and a loading and unloading area in front of the building (**Exhibits B2.2 and B4**). Staff is recommending a condition of approval to have no less than 10 parking spaces to accommodate employees and customers in accordance with CCCO Section 07-13-03. *See the conditions of approval numbers 7 and 9a.* • Restrooms: The applicant is proposing to have one (1) restroom on-site for customers and employees (**Exhibit B2.2**). *See condition number 10.* • Waste Disposal: The applicant will contract with the business "Darling", which provides a container for the meat by-products (including bones). "Darling" will pick up the animal by-product twice a week to use for animal food and other products (**Exhibits B2.1, B2.2, and B2.3**). The applicant will recycle the manure into his pasture, which will continue to be used for the property owner's livestock (**Exhibit B2.3**).	

	The preliminary septic permit for the slaughterhouse that was issued and approved by Southwest District Health and the Department of Environmental Quality accounted for the blood waste (**Exhibit E8.3**). • Traffic: The applicant anticipates approximately 20 customer vehicles a week (**Exhibit B2.2**). • Retail: The proposal includes a retail space of approximately 100 sq ft to sell meat from the slaughter (**Exhibit B2.2**). As conditioned, the retail space shall not expand greater than 400 sq ft. *See condition number 7b.* Staff spoke to the Food Department within Southwest District Health on April 28, 2026. The applicant is required to submit a Plan Review Application. The results from the Plan Review Application will determine the regulation requirements through Southwest District Health and the U.S. Department of Agriculture. Southwest District Health provided additional resources on April 29, 2026 (**Exhibit E9**). Idaho's Licensing Guidance Table for Food Processing and Storage states that the Health District will license and inspect for the first year of operation, with some exceptions. After the first year of operation, the facility may be referred to the FDA for jurisdiction. It also specifies that custom meat processing is the USDA's jurisdiction, except for any retail sales, which are licensed by the health department. USDA inspection does not extend to retail sales of meat (**Exhibit E9.1**). The USDA Information explained the jurisdiction and exceptions in regard to a slaughterhouse (**Exhibit E9.2**). The applicant will be required to obtain the required food permits and meet all applicable requirements of the U.S. Department of Agriculture (USDA) prior to beginning operations. *See condition numbers 10a and 14.*
Criteria Met? **Yes**	**3**	**Is the proposed use consistent with the comprehensive plan?**
Analysis	The proposed use is consistent with the Comprehensive Plan. The Future Land Use Map in the 2030 Canyon County Comprehensive Plan designates the subject parcel and the surrounding area as "Agriculture" with an "Intensive Agriculture Overlay" (**Exhibit C2.5**). A slaughterhouse would be compatible with the uses outlined in the description for what the intensive agriculture overlay is intended to protect. • 2030 Canyon County Comprehensive Plan describes the intensive agriculture overlay as "*This overlay is applied to protect working lands and operations. These areas may have higher quality soils, water availability, and relatively flat topography. Uses may include seed production, crops, orchards, vineyards, concentrated animal feeding operations, grazing, and other agriculturally-based uses. This designation aims to protect agriculture operations from incompatible uses and reduce the conflicts concerning noise, dust, smells, and safety.*" Approximately 2.50 miles west of the subject property, there is a future land use designation of "Commercial" (**Exhibit C2.15**). Payette County is east of the subject property on the other side of Hwy 95. Payette County's Future Land Use designates this area primarily for "Agricultural Preservation" with some "Industrial" and "Agriculture Mixed" (**Exhibit C3**). As conditioned, the proposed use is aligned with the following goals and policies of the 2030 Comprehensive Plan: • Property Rights Goals: ○ G1.01.00: *"Protect the integrity of individual property rights while safeguarding public health, safety, and welfare."*	

- G1.02.00: *"Acknowledge the responsibilities of each property owner as a steward of the land, use their property wisely, maintain it in good condition, and preserve it for future generations without becoming a public nuisance."*

Canyon County values the applicants' and surrounding property owners' private property rights and may support the applicants' project and the surrounding property owners' rights by adding mitigating conditions to the proposed conditional use permit (CCCO Section 07-07-17). *See the proposed conditions on page 9.*

- Economic Development Goals and Policies:
  - G3.01.00: *"Promote a healthy and sustainable regional economy by retaining, expanding, and recruiting businesses to favorable locations."*
  - P3.01.02: *"Support suitable sites for economic growth and expansion compatible with the surrounding area."*
  - G3.04.00: *"Increase agricultural-based and supportive businesses."*
  - G3.05.00: *"Support a diverse economy in Canyon County and recognize that residential, commercial, and industrial uses are necessary components of overall economic stability."*

Canyon County supports retaining, expanding, and recruiting businesses and economic growth and expansion, but this must be done in a way that is compatible with the surrounding area, which may include adding mitigation conditions to this conditional use permit that address the community's concerns (noise, traffic, dust, etc.). *See the proposed conditions on page 9.*

- Land Use Goals and Policies:
  - P4.01.01: *"Maintain a balance between residential growth and agriculture that protects the rural character."*
  - *P4.01.02: "Planning, zoning, and land-use decisions should balance the community's interests and protect private property rights."*
  - P4.02.01: *"Consider site capability and characteristics when determining the appropriate locations and intensities of various land uses."*
  - *G4.05.00: "Support a diversity of agricultural uses to sustain the agricultural and agriculturally related economy."*

Canyon County supports growth and development as long as it is compatible with the surrounding area and appropriate conditions are added to mitigate adverse impacts that affect other land uses and the surrounding community. *See the proposed conditions on page 9.*

- Agriculture Goals and Policies:
  - G12.01.00: *"Protect agricultural lands for long-term agricultural production from encroachment of incompatible uses."*
  - *P12.01.04: "Prioritize the protection of agriculture and farmlands in Canyon County as an essential part of the County's economy, identity, and sense of place."*
  - *G12.02.00: "Support farmers and enhance local farmland."*

Canyon County supports preserving agricultural lands, farming activities, and farming-related businesses as long as it is compatible with the surrounding area and appropriate conditions are added to mitigate adverse impacts that affect other land uses and the surrounding community. *See the proposed conditions on page 9.*

Criteria Met?	4	Will the proposed use be injurious to other property in the immediate vicinity and/or negatively change the essential character of the area?
Yes		

Analysis

As conditioned, the proposed use will not be injurious to other property in the immediate vicinity and will not negatively change the essential character of the area.

Summary:
The surrounding land uses within a one-mile radius indicate that the land use in the area primarily is agricultural (**Exhibits C2.5, C2.7, C2.8, and C4**). Although there are some residential properties in the area, the majority have agricultural operations. There are agricultural operations adjacent to the subject property on all sides. A slaughterhouse is allowed in an agricultural zone with a conditional use permit. As conditioned, the proposed use is not anticipated to be injurious to other property within the immediate vicinity, nor negatively change the essential character of the area.

Adjacent Existing Conditions:

Direction	Existing Use	Primary Zone	Other Zone
N	Agricultural Operation	"A"	
S	Agricultural Operation	"A"	"M1", "C2", "RR", and "R1"
E	Payette County	Agriculture	Industrial
W	Agricultural Operation and Applicant's Primary Residence	"A"	"RR"

"A" (Agricultural), "R-R" (Rural Residential), "R-1" (Single-Family Residential), "C-1" (Neighborhood Commercial), "C-2" (Service Commercial), "M-1" (Light Industrial), "CR" (Conditional Rezone)

Surrounding Land Use Cases:
There have been four (4) platted subdivisions approved (**Exhibit C2.7**) in a 1-mile radius from the subject property. All the subdivisions were platted in the early 1900's. There are no other approved developments in the area.

Character of the Area:
The area is characterized as agricultural. The subject property is adjacent to agricultural operations on all sides. Within 1,000 feet of the subject property, there are 18 properties within Canyon County and Payette County, all located on agriculturally zoned parcels.

Within a 2-mile radius of the subject property, there are two (2) feedlots and one (1) dairy (**Exhibit C2.8**).

The soil classification on the subject property is primarily classified as moderately suited soil (class 4) and least suited soil (class 6) (**Exhibit C2.10**). The proposal utilizes an agriculturally zoned property that doesn't have the best-suited soils to support livestock production.

Potential Impacts:
The slaughterhouse may impact the surrounding area due to the increase in waste, dust, traffic, odor/smell, and lighting related to the use. Staff has proposed conditions to aid in mitigating these potential effects.

The increase in waste has the potential to impact the surrounding area. The applicant is proposing to contract with a company that will pick up the animal byproduct twice a week to use for animal feed (**Exhibits B2.1 and B2.2**). The applicant must meet the waste disposal requirements of the Department of Environmental Quality (DEQ). *See the conditions of approval numbers 1a, 1b, and 1c.*

The proposed use may increase the dust levels in the immediate vicinity. Dust shall be controlled in accordance with applicable federal, state, and county laws, ordinances, rules, and regulations pertaining to operations and shall be consistent with Idaho Department of Environmental Quality (DEQ) requirements. To

	mitigate the potential for dust, the applicant shall submit a dust mitigation plan for staff's review and approval prior to commencement. The applicant must also pave the parking spaces. *See the conditions of approval numbers 9 and 9a.* The proposed use may cause an odor in the immediate vicinity. Canyon County doesn't have any specific code or regulations regarding odors/smells. However, Canyon County's CAFO regulations has further setbacks for animal waste systems if near a residence (CCCO §08-01-12(1)C). Although the request is not for a CAFO, staff is recommending the same setback requirements to mitigate the odor/smell, "The animal waste system shall not be located closer than five hundred feet (500') from an existing residence belonging to someone other than the applicant, or be located and/or operated closer than one hundred feet (100') from the property lines, unless the owner gives written consent to a shorter distance." It appears that the applicant is already meeting this setback requirement with no existing residence located within 500 feet of the proposed use. *See condition number 15.* As conditioned, all exterior lighting, if installed, shall be downward-facing and directed away from surrounding properties. Compliance shall be demonstrated in the building plans submitted as part of the building permit submittal. Review and approval by DSD shall be completed before building permit issuance. *See the condition of approval number 4.* See CCCO §07-07-05(7) for potential traffic impact analysis.	
Criteria Met? **Yes**	**5**	**Will adequate water, sewer, irrigation, drainage and stormwater drainage facilities, and utility systems be provided to accommodate the use?**
Analysis	The project will have adequate water, sewer, irrigation, drainage, and stormwater drainage facilities, and utility systems to accommodate the proposed use based on the analysis contained herein. **Water:** The property appears to have adequate water via an individual well. There are no additional wells proposed to serve the proposed slaughterhouse (**Exhibit B4**). Idaho Department of Water Rights (IDWR) commented on April 7, 2026, stating that the proposed use would be able to be supplied by the existing domestic well as long as water does not exceed 2,500 gallons per day. If the use exceeds the maximum amount allowed, the applicant will need to obtain a commercial water right. The area is open for new water rights, and after conducting a preliminary check, Idaho Department of Water Rights (IDWR) does not see any areas of concern (**Exhibit E4**). The existing water uses are anticipated to provide adequate water for the proposed use. *See the condition of approval number 13.* **Sewer:** The applicant is proposing to have one restroom on-site for customer and employee use (**Exhibit B2.2**). Comment from Southwest District Health on April 22, 2026, advised that a preliminary subsurface sewage disposal permit has been issued and is consistent with the total wastewater design flow specified in the approved letter of intended use (**Exhibit E8**). The pre-development notes specified that the letter of intended use was submitted and approved by Southwest District Health and Idaho Department of Environmental Quality (DEQ). It was also identified that the originally proposed drain field location encroaches into an area subject to vehicle traffic, which may result in soil compaction and compromised system performance. New test holes will be required in an alternate location to evaluate site suitability for a revised drain field area that avoids vehicle traffic impacts (**Exhibit E8.1**). The approved preliminary septic permit can be seen in **Exhibit E8.2**. *See the condition of approval number 10.* Pre-Development Notes from Southwest District Health advises that the proposed drain field area must maintain a minimum setback of at least 50 feet from the canal (**Exhibit E8.1**). **Waste Disposal:**	

	The applicant will contract with the business "Darling", which provides a container for the meat by-products (including bones). "Darling" will pick up the animal by-product twice a week to use for animal food and other products (**Exhibits B2.1, B2.2, and B2.3**). The applicant will recycle the manure into his pasture, which will continue to be used for the property owner's livestock (**Exhibit B2.3**). The preliminary septic permit for the slaughterhouse that was issued and approved by Southwest District Health and the Department of Environmental Quality accounted for the blood waste (**Exhibit E8.3**). **Irrigation:** Agency notice was sent out to Farmers Cooperative Ditch Company and Black Canyon Irrigation District on November 14, 2025, and April 16, 2026. A comment letter received from Farmers Cooperative Ditch Company on April 8, 2026, advised that the proposed use should not impact the water quality or surface runoff, and requests that there are safeguards in place for animal waste to not run into the canal (**Exhibit E5**). No comments were received from Black Canyon Irrigation District. *Condition number 5* ensures the applicant shall not impede, disrupt, or disturb the existing irrigation structure without approval from the irrigation district. *See the conditions of approval numbers 1a, 1b, and 1c* to manage the concern of animal waste running into the canal. **Stormwater drainage facilities:** As conditioned, stormwater will be retained onsite. *See the condition of approval number 12.* **Utility Systems:** Utility agencies, including Idaho Power, Intermountain Gas, CenturyLink, and Ziply, were notified of the application on November 14, 2025, and April 16, 2026. No agency comments were provided by those services at the time the staff report was written. It is anticipated that the applicant will be able to work with utility providers to gain any additional utilities needed.	
Criteria Met? **Yes**	**6**	**Does legal access to the subject property for the development exist or will it exist at the time of development?**
Analysis	The subject property will have legal access at the time of the development. Access to the facility is proposed to utilize Hwy 95 (**Exhibit B7**). The subject property has an old farm field approach. The approach will not meet the current standards of Idaho Transportation Department. Therefore, a new access point will be required (**Exhibit E2.2**). According to a comment letter received from the Idaho Transportation Department, an approach permit application is required and access is required to be constructed to meet the current specs of a commercial two-way approach (**Exhibit E2**). *See condition number 3.*	
Criteria Met? **Yes**	**7**	**Will there be undue interference with existing or future traffic patterns?**
Analysis	Undue interference with the existing or future traffic patterns is not anticipated. Any potential impact will be reviewed by Idaho Department of Transportation (ITD). It is anticipated that there will be a maximum of eight (8) employees and approximately 20 vehicles a week (**Exhibits B2.2 and B4**). The subject property takes access from Hwy 95, which is serviced by the Idaho Transportation Department (ITD). ITD's comment received on April 6, 2026, states that the proposal is for a relatively small operation and does not expect to have any traffic concerns related to the proposal. ITD's trip generation estimates approximately 16 vehicles during AM peak hours and 13 vehicles during PM peak hours (**Exhibit E2.1**). *See condition number 3.* Based on the traffic information from ITD, the proposed use is not anticipated to cause any undue impact to the existing or future traffic patterns.	

Criteria Met?	8	Will essential services be provided to accommodate the use including, but not limited to, school facilities, police and fire protection, emergency medical services, irrigation facilities, and will the services be negatively impacted by such use or require additional public funding in order to meet the needs created by the requested use?
Yes		
Analysis	Essential services will be provided to accommodate the use, including, but not limited to, school facilities, police and fire protection, emergency medical services, and irrigation facilities. The services will not be negatively impacted by such use or require additional public funding in order to meet the needs created by the requested use. **School Facilities:** Parcel R39357012 is serviced by the Parma School District. It is not anticipated that any impact or accommodations will be needed for the proposed use. Agency comments were sent out on November 14, 2025, and April 16, 2026. No comments were received by the school district. **Police and Fire Protection:** Parcel R39357012 is under the jurisdiction of the Parma Fire District. Parma Fire District is required to provide services to the parcel. As conditioned, the applicant shall comply with all Fire District requirements per State adopted IFC, and as evidenced by review and approval documentation from the applicable fire district prior to issuance of a certificate of occupancy and commencement of activities on the site. All development shall comply with the 2018 International Fire Code and codes set forth by Canyon County. *See condition number 11.* Agency notice was sent on November 14, 2025, and April 16, 2026. Parma Fire District provided comment on May 4, 2026, advising that the response time to the subject property is approximately 5 minutes (**Exhibit E11**). No comment was received from the Canyon County Sheriff's Department. **Emergency Medical Services:** Emergency Medical Services are provided to the property. Canyon County Paramedics/EMT and Canyon County's Emergency Management were notified of the application on November 14, 2025, and April 16, 2026. Canyon County Paramedics/EMT provided their response times to the subject property on May 1, 2026. The response times vary from 25.02 minutes, 27.10 minutes, and 28.30 minutes. It was advised that the Parma Fire District would have a faster response time to the subject property (**Exhibit E10**). No comment was received from Canyon County's Emergency Management. Overall, the use is not anticipated to be significant enough to cause a negative impact or require additional public funding. **Irrigation Facilities:** Agency notice was sent out to Farmers Cooperative Ditch Company and Black Canyon Irrigation District on November 14, 2025, and April 16, 2026. A comment letter received from Farmers Cooperative Ditch Company on April 8, 2026, advised that the proposed use should not impact the water quality or surface runoff, and requests that there are safeguards in place for animal waste to not run into the canal (**Exhibit E5**). No comments were received from Black Canyon Irrigation District. *Condition number 5* ensures the applicant shall not impede, disrupt, or disturb the existing irrigation structure without approval from the irrigation district. *See the conditions of approval numbers 1a, 1b, and 1c* to manage the concern of animal waste running into the canal.	

NOTIFICATION AND COMMENTS:
Notice of the public hearing was provided as per CCCO §07-05-01. Agencies were notified on November 14, 2025, and April 16, 2026. Property owners in Canyon County within 1,000 feet of the subject property boundaries were notified on April 16, 2026. Property owners in Payette County within 1,000 feet of the subject property boundaries were notified on April 28, 2026. A newspaper notice was published on April 21, 2026. The subject property was posted with a notice on April 22, 2026.

Pursuant to CCCO §01-17-07B - Materials Deadline, the submission of late documents or other materials does not allow all parties time to address the materials or allow sufficient time for public review. After the materials deadline, any input may be verbally provided at the public hearing to become part of the record.

AGENCY COMMENTS
All agency comments received by the aforementioned materials deadline are located in Exhibit E.

PUBLIC COMMENTS
Staff received five (5) total written public comments and one (1) petition with five (5) signatures by the materials deadline of May 11, 2026. Generally, of the comments received, one (1) was in favor, zero (0) were neutral, and four (4) plus the petition were opposed. All public comments received by the aforementioned materials deadline are located in Exhibit F.

RECOMMENDATION AND DECISION OPTIONS:

In consideration of the application and supporting materials, staff concludes that the proposed Conditional Use Permit is compliant with Canyon County Ordinance 07-07-05. A full analysis is detailed within the staff report.

Should the Commission wish to approve the subject application, staff recommends the following conditions be attached:

1. The development shall comply with all applicable federal, state, and county laws, ordinances, rules, and regulations that pertain to the subject property and the proposed use.
    a. Water (including surface, groundwater, and stormwater) shall be discharged in accordance with state, federal, and local standards and/or regulations.
    b. The operator shall dispose of waste in a manner that does not contribute to potential environmental and water contamination in and around the subject property.
    c. The applicant shall coordinate with the Department of Environmental Quality (DEQ) to manage on-site waste products and disposal. Evidence shall be a letter of review and approval from DEQ, provided prior to commencement of use (**Exhibit E1**).
    d. The applicant shall meet Canyon County's GIS Department requirements prior to beginning operations (**Exhibit E6**).
2. The applicant shall obtain a commercial building permit for the slaughterhouse prior to commencement of use.
    a. The applicant shall appropriately permit the agriculture (AG) building within **180 days of the approval of the Conditional Use Permit** (**Exhibit E7**).
    b. Development on slopes 15% or greater, as shown in the USGS Map (**Exhibit C2.14**), requires a preliminary engineered grading and drainage plan for any development (grading, road construction, and structures) to be submitted prior to building issuance in compliance with §07-17-33(1)C. Applicable regulations and standards of the stated code shall be determined by the County Engineer, and the plan shall be reviewed and approved by the County Engineer. Any review fees

shall be paid by the applicant prior to building permit issuance. A final engineered grading and drainage shall be submitted prior to the certificate of occupancy.

3. The applicant shall comply with applicable Idaho Department of Transportation (ITD) requirements prior to operations (**Exhibit E2**).
    a. An approved approach permit shall be obtained prior to commencement of the use for the proposed access, as evidenced by the applicant providing Development Services with an approved Idaho Department of Transportation (ITD) document indicating the completion of improvements.
4. All exterior lighting, if installed, shall be downward-facing and directed away from surrounding properties. Compliance shall be demonstrated in the building plans submitted as part of the building permit submittal via an exterior lighting plan. Review and approval by DSD shall be completed before building permit issuance.
5. The applicant shall not impede, disrupt, or otherwise disturb the existing irrigation structures on and adjacent to the subject property and easement without written approval from the irrigation district with jurisdiction.
6. Signage shall meet CCCO §07-10-13 requirements and shall not exceed 32 sq. feet and 10 feet in height unless an additional sign permit is applied for and approved by the Director. If it exceeds 6 ft in height, a building permit is required.
7. The proposed development shall be in general conformance with the applicant's site plan and letter of intent (**Exhibits B2, B2.1, and B3**).
    a. Employees' vehicles shall be parked on-site and not on a public or private road. Business vehicles shall be operable and parked on site, not on a public or private road.
    b. The proposed retail sales shall stay as an accessory use to the slaughterhouse and shall not exceed 400 sq. ft in size.
    c. The applicant must have no less than 10 parking spaces on-site in accordance with CCCO Section 07-13-03.
    d. The hours of operation shall be Monday through Saturday, 7 am – 5 pm (**Exhibit B4**).
8. This conditional use permit must follow land use time limitation as stated in CCCO 07-07-23: "When a conditional use permit is granted, the land use or construction of its facility proposed in the application must have commenced within three (3) years of the date of the final decision by the presiding party or a court of appropriate jurisdiction. The improvements for the approved use must be completed within five (5) years of the same date.
9. A dust mitigation plan shall be provided prior to commencement of use to the Development Services Department. Dust shall be controlled in accordance with applicable federal, state, and county laws, ordinances, rules, and regulations pertaining to operations and shall be consistent with Idaho Department of Environmental Quality (DEQ) requirements.
    a. The applicant shall pave the parking area (**Exhibit B2.2**).
10. The applicant shall meet all applicable Southwest District Health (SWDH) requirements for the proposed use. Evidence shall be a letter of review and approval from SWDH, provided prior to commencement of use (**Exhibit E8.1**).
    a. The applicant shall obtain the required food permits prior to beginning operations unless waived (**Exhibit E9.1**).

11. The applicant shall comply with all fire district requirements per State adopted IFC and as evidenced by review and approval documentation from Parma Fire District prior to commencement of use.
12. The applicant shall retain stormwater drainage onsite.
13. The applicant shall obtain commercial water rights for the proposed use through the Idaho Department of Water Rights (IDWR) if the proposed use exceeds 2,500 gallons per day (**Exhibit E4**).
14. The applicant shall meet all applicable U.S. Department of Agriculture (USDA) requirements for the proposed use. Evidence shall be a letter of review and approval from USDA, provided prior to commencement of use (**Exhibit E9.2**).
15. Waste System Setbacks:
    a. The animal waste system shall not be located closer than five hundred feet (500') from an existing residence belonging to someone other than the applicant, or be located and/or operated closer than one hundred feet (100') from the property lines, unless the other owner gives written consent to a shorter distance.
    b. No animal waste system shall be located closer than one hundred feet (100') from a domestic or irrigation well.
    c. No animal waste system shall be located closer than one hundred feet (100') from a public right of way.
16. The conditional use for the slaughterhouse shall be limited to Lucus Hansen and family. Should ownership of parcel R39357012 change from Lucus Hansen or an immediate family member, the conditional use permit for a slaughterhouse shall terminate.

ALTERNATE CONDITION:

16. The conditional use for the slaughterhouse shall be limited to Lucus Hansen and family. Should ownership of parcel R39357012 change from Lucus Hansen or an immediate family member, the new property owner shall provide Development Services Department with notarized consent to the slaughterhouse conditions.

<u>DECISION OPTIONS</u>

- **Approval of the Application**: "I move to approve CU2025-0031, Hansen, finding the application **does** meet the criteria for approval under Article 07-07-05 of Canyon County Zoning Ordinance, **with the conditions listed in the staff report, finding that**: [*Cite reasons for approval & Insert any additional conditions of approval*].
- **Denial of the Application**: "I move to deny CU2025-0031, Hansen, finding the application **does not** meet the criteria for approval under Article 07-07-05 of Canyon County Zoning Ordinance, **finding that** [*cite findings for denial based on the express standards outlined in the criteria & the actions, if any, the applicant could take to obtain approval (ref.ID.67-6519(5)*].
- **Table the Application:** "I move to continue CU2025-0031, Hansen to a [*date certain or uncertain*]

EXHIBITS:

A. **Draft FCOS**
B. **Application Packet & Supporting Materials**
    1. Master Application
    2. Letter of Intent
        2.1. Email Correspondence; February 4, 2026
        2.2. Email Correspondence; April 6, 2026
        2.3. Phone Conversation; April 29, 2026
    3. Site Plan
    4. Land Use Worksheet
    5. Neighborhood Meeting
    6. Agency Acknowledgement
    7. Access Location
    8. Preliminary Site Plan; Received: May 11, 2026
C. Supplemental Documents
    1. Parcel Information Report
    2. Case Maps/Reports
        2.1. Aerial
        2.2. Small Air Photo 1 Mile
        2.3. FEMA Small Air Photo
        2.4. Small Vicinity Map
        2.5. Zoning & Classification Map
        2.6. Case Map & Summary
        2.7. Subdivision Map & Report
        2.8. Dairy, Feedlot, & Gravel Pit Map
        2.9. Lot Classification Map
        2.10. Soil & Prime Farmland Maps & Report
        2.11. Contour Map
        2.12. Nitrate Priority & Wells Map
        2.13. TAZ Household & Job Maps
        2.14. Slope Percent Map
        2.15. Future Land Use Map
        2.16. Notification Map
        2.17. Payette Notification Map
    3. Payette County Future Land Use Map
    4. Payette County Current Zoning Map
D. Site Visit Photos: March 25, 2026
E. Agency Comments Received by: May 11, 2026
    1. DEQ; Received: December 1, 2025
    2. ITD – Access; Received: December 4, 2025
        2.1. ITD – Traffic; Received: April 7, 2026
        2.2. ITD – New Access; Received: April 28, 2026
    3. Idaho State Department of Agriculture; Received: April 7, 2026
    4. Idaho Department of Water Rights; Received: April 7, 2026
    5. Farmers Cooperative Ditch Company; Received: April 8, 2026
    6. CC GIS Department; Received: April 16, 2026
    7. CC Building Department; Received: April 21, 2026
    8. Southwest District Health – Septic; Received: April 22, 2026
        8.1. Pre-Development Notes
        8.2. Preliminary Septic Permit
        8.3. Blood Waste; Received: April 29, 2026

9. Southwest District Health – Food; Received: April 29, 2026
    9.1. Idaho's Licensing Guidance Table – Food Processing & Storage
    9.2. USDA Information – Jurisdiction and Exemptions
10. CC Paramedics/EMT; Received: May 1, 2026
11. Parma Fire District, Received: May 4, 2026

F. Public Comments Received by: May 11, 2026

1. Growing Together – In Favor; Received: April 27, 2026
2. Mike & Charlie Sety – In Opposition; Received: May 8, 2026
3. Jennifer McClain – In Opposition; Received: May 11, 2026
4. Richard & Sheila Hartshorn – In Opposition; Received: May 11, 2026
5. Kevin Olinger – In Opposition; Received: May 11, 2026
6. Petition w/ 5 Signatures – In Opposition; Received: May 11, 2026

Exhibit A:

EXHIBIT A

Draft FCOs

Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 21, 2026

In the matter of the application of:
Hansen – CU2025-0031

The Canyon County Planning and Zoning Commission considers the following:

Case No. CU2025-0031: The applicant, Lucus Hansen, is requesting a Conditional Use Permit for a Slaughterhouse on approximately 11.30 acres in an "A" (Agricultural) zone. The request is for a custom slaughterhouse in which the applicant will accept animals from customers for processing. The request includes retail sales as an accessory use to the slaughterhouse. Proposed hours of operation for the slaughterhouse and retail sales are Monday – Saturday, 7 am to 5 pm. The subject property is located at 0 Hwy 95, Parma, also referenced as Parcel R39357012, a portion of the NE quarter of Section 20, T6N, R5W, BM, Canyon County, Idaho.

Summary of the Record

1. The record is comprised of the following:

   A. The record includes all testimony, the staff report, exhibits, and documents in Case File CU2025-0031.
      1. All exhibits are located in the case staff report dated May 21, 2026.

Applicable Law

1. The following laws and ordinances apply to this decision: Canyon County Code of Ordinances (CCCO) §01-17 (Land Use/Land Division Hearing Procedures), CCCO §07-05 (Notice, Hearing and Appeal Procedures), CCCO §07-07 (Conditional Use Permits), CCCO §07-02-03 (Definitions), CCCO §07-10-27 (Land Use Regulations (Matrix)), CCCO §07-14 (Use Standards), and Idaho Code §67-6512 (Special Use Permits, Conditions, and Procedures).

   a. Notice of the public hearing was provided pursuant to CCCO §07-05-01, Idaho Code §67-6509 and 67-6512.

   b. A special use permit may be granted to an applicant if the proposed use is conditionally permitted by the terms of the ordinance, subject to conditions pursuant to specific provisions of the ordinance, subject to the ability of political subdivisions, including school districts, to provide services for the proposed use, and when it is not in conflict with the plan. Idaho Code §67-6512.

   c. Every use which requires the granting of a conditional use permit is declared to possess characteristics which require review and appraisal by the commission to determine whether or not the use would cause any damage, hazard, nuisance or other detriment to persons or property in the vicinity. *See* CCCO §07-07-01.

   d. Upon the granting of a special use permit, conditions may be attached to a special use permit including, but not limited to, those: (1) Minimizing adverse impact on other development; (2) Controlling the sequence and timing of development; (3) Controlling the duration of development; (4) Assuring that development is maintained properly; (5) Designating the exact location and nature of development;(6) Requiring the provision for on-site or off-site public facilities or services; (7) Requiring more restrictive standards than those generally required in an ordinance; (8) Requiring mitigation of effects of the proposed development upon service delivery by any political subdivision, including school

districts, providing services within the planning jurisdiction. *See* Idaho Code §67-6512, CCCO §07-07-17, and 07-07-19.

2. The commission shall have those powers and perform those duties assigned by the board that are provided for in the local land use planning act, Idaho Code, title 67, chapter 65, and county ordinances. CCCO §07-03-01, 07-07-01.

3. There are no mandates in the Local Planning Act as to when conditional permits may or may not be granted, aside from non-compliance with the community master plan. I.C. § 67-6512. Chambers v. Kootenai Cnty. Bd. of Comm'rs, 125 Idaho 115, 117, 867 P.2d 989, 991 (1994).

4. The burden of persuasion is upon the applicant to prove that all criteria are satisfied. CCCO §07-05-03.

5. Idaho Code §67-6535(2) requires the following: The approval or denial of any application required or authorized pursuant to this chapter shall be in writing and accompanied by a reasoned statement that explains the criteria and standards considered relevant, states the relevant contested facts relied upon, and explains the rationale for the decision based on the applicable provisions of the comprehensive plan, relevant ordinance and statutory provisions, pertinent constitutional principles and factual information contained in the record.

6. The County's hearing procedures adopted per Idaho Code §67-6534 require that final decisions be in the form of written findings, conclusions, and orders. CCCO 07-05-03(1)(I).

The application, CU2025-0031, was presented at a public hearing before the Canyon County Planning and Zoning Commission on May 21, 2026. Having considered all the written and documentary evidence, the record, the staff report, oral testimony, and other evidence provided, including the conditions of approval and project plans, the Canyon County Planning and Zoning Commission decide as follows:

Table 1. Conditional Use Permit Standards of Evaluation Analysis

Standards of Evaluation – CCCO §07-07-05: The presiding party shall consider each conditional use permit application by finding adequate evidence to answer the following questions in its FCOs:		
County Ordinance and Review		
Criteria Met?	**Code Section**	**Criteria**
Yes	**1**	**Is the proposed use permitted in the zone by conditional use permit?**
Analysis	The proposed use for a slaughterhouse is permitted in the zone by a conditional use permit, pursuant to CCCO §07-10-27. The applicant submitted a conditional use permit for a slaughterhouse on November 10, 2025. *See* ***Staff Report Exhibit A*** *for the application and submitted materials.* • CCCO §07-02-03 defines a slaughterhouse as *"A facility where animals are killed and may be processed into meat products.*" See project description analysis contained in Section 07-07-05(2) detailing the nature of the request.	
Criteria Met? **Yes**	**2**	**What is the nature of the request?**
Analysis	The property owner, Lucus Hansen, requests a conditional use permit to establish a slaughterhouse on an approximately 11.30-acre parcel in the "A" (Agricultural) zone, designated as parcel R39357012. • Use: The nature of the request consists of using the subject property to conduct the applicant's slaughterhouse business. The applicant anticipates slaughtering approximately 10 animals per week; the animals will be mostly beef and pigs. The proposed building is 60 feet by 100 feet. Located behind the proposed building is a pasture and a holding pen. The facility will include a restroom, a breakroom, and a retail store selling the processed meat as an accessory to the slaughterhouse (**Staff Report Exhibits B2, B2.1, B2.2, and B3**). • Number of Employees: The applicant is proposing to have a maximum of eight (8) employees. (**Staff Report Exhibit B4**).	

	• Hours of Operation: The hours of operation proposed are Monday through Saturday from 7 am to 5 pm (**Staff Report Exhibit B4**). • Parking: According to email correspondence and the land use matrix, the applicant is proposing five to six (5 to 6) paved parking spaces and a loading and unloading area in front of the building (**Staff Report Exhibits B2.2 and B4**). Staff is recommending a condition of approval to have no less than 10 parking spaces to accommodate employees and customers in accordance with CCCO Section 07-13-03. *See the conditions of approval numbers 7 and 9a.* • Restrooms: The applicant is proposing to have one (1) restroom on-site for customers and employees (**Staff Report Exhibit B2.2**). *See condition number 10.* • Waste Disposal: The applicant will contract with the business "Darling", which provides a container for the meat by-products (including bones). "Darling" will pick up the animal by-product twice a week to use for animal food and other products (**Staff Report Exhibits B2.1, B2.2, and B2.3**). The applicant will recycle the manure into his pasture, which will continue to be used for the property owner's livestock (**Staff Report Exhibit B2.3**). The preliminary septic permit for the slaughterhouse that was issued and approved by Southwest District Health and the Department of Environmental Quality accounted for the blood waste (**Staff Report Exhibit E8.3**). • Traffic: The applicant anticipates approximately 20 customer vehicles a week (**Staff Report Exhibit B2.2**). • Retail: The proposal includes a retail space of approximately 100 sq ft to sell meat from the slaughter (**Staff Report Exhibit B2.2**). As conditioned, the retail space shall not expand greater than 400 sq ft. *See condition number 7b.* Staff spoke to the Food Department within Southwest District Health on April 28, 2026. The applicant is required to submit a Plan Review Application. The results from the Plan Review Application will determine the regulation requirements through Southwest District Health and the U.S. Department of Agriculture. Southwest District Health provided additional resources on April 29, 2026 (**Staff Report Exhibit E9**). Idaho's Licensing Guidance Table for Food Processing and Storage states that the Health District will license and inspect for the first year of operation, with some exceptions. After the first year of operation, the facility may be referred to the FDA for jurisdiction. It also specifies that custom meat processing is the USDA's jurisdiction, except for any retail sales, which are licensed by the health department. USDA inspection does not extend to retail sales of meat (**Staff Report Exhibit E9.1**). The USDA Information explained the jurisdiction and exceptions in regard to a slaughterhouse (**Staff Report Exhibit E9.2**). The applicant will be required to obtain the required food permits and meet all applicable requirements of the U.S. Department of Agriculture (USDA) prior to beginning operations. *See condition numbers 10a and 14.*
Criteria Met? **Yes**	**3** **Is the proposed use consistent with the comprehensive plan?**
Analysis	The proposed use is consistent with the Comprehensive Plan. The Future Land Use Map in the 2030 Canyon County Comprehensive Plan designates the subject parcel and the surrounding area as "Agriculture" with an "Intensive Agriculture Overlay" (**Staff Report Exhibit C2.5**). A slaughterhouse would be compatible with the uses outlined in the description for what the intensive agriculture overlay is intended to protect. • *2030 Canyon County Comprehensive Plan describes the intensive agriculture overlay as "This overlay is applied to protect working lands and operations. These areas may have higher quality soils, water availability, and relatively flat topography. Uses may include seed production, crops, orchards, vineyards, concentrated animal feeding operations, grazing, and other agriculturally-*

based uses. This designation aims to protect agriculture operations from incompatible uses and reduce the conflicts concerning noise, dust, smells, and safety."

Approximately 2.50 miles west of the subject property, there is a future land use designation of "Commercial" (**Staff Report Exhibit C2.15**).

Payette County is east of the subject property on the other side of Hwy 95. Payette County's Future Land Use designates this area primarily for "Agricultural Preservation" with some "Industrial" and "Agriculture Mixed" (**Staff Report Exhibit C3**).

As conditioned, the proposed use is aligned with the following goals and policies of the 2030 Comprehensive Plan:

- Property Rights Goals:
  - G1.01.00: *"Protect the integrity of individual property rights while safeguarding public health, safety, and welfare."*
  - G1.02.00: *"Acknowledge the responsibilities of each property owner as a steward of the land, use their property wisely, maintain it in good condition, and preserve it for future generations without becoming a public nuisance."*

  Canyon County values the applicants' and surrounding property owners' private property rights and may support the applicants' project and the surrounding property owners' rights by adding mitigating conditions to the proposed conditional use permit (CCCO Section 07-07-17). *See the conditions of approval.*

- Economic Development Goals and Policies:
  - G3.01.00: *"Promote a healthy and sustainable regional economy by retaining, expanding, and recruiting businesses to favorable locations."*
  - P3.01.02: *"Support suitable sites for economic growth and expansion compatible with the surrounding area."*
  - G3.04.00: *"Increase agricultural-based and supportive businesses."*
  - G3.05.00: *"Support a diverse economy in Canyon County and recognize that residential, commercial, and industrial uses are necessary components of overall economic stability."*

  Canyon County supports retaining, expanding, and recruiting businesses and economic growth and expansion, but this must be done in a way that is compatible with the surrounding area, which may include adding mitigation conditions to this conditional use permit that address the community's concerns (noise, traffic, dust, etc.). *See the conditions of approval.*

- Land Use Goals and Policies:
  - P4.01.01: *"Maintain a balance between residential growth and agriculture that protects the rural character."*
  - *P4.01.02: "Planning, zoning, and land-use decisions should balance the community's interests and protect private property rights."*
  - P4.02.01: *"Consider site capability and characteristics when determining the appropriate locations and intensities of various land uses."*
  - *G4.05.00: "Support a diversity of agricultural uses to sustain the agricultural and agriculturally related economy."*

  Canyon County supports growth and development as long as it is compatible with the surrounding area and appropriate conditions are added to mitigate adverse impacts that affect other land uses and the surrounding community. *See the conditions of approval.*

- Agriculture Goals and Policies:

<table>
<tr><td></td><td colspan="2">

G12.01.00: “Protect agricultural lands for long-term agricultural production from encroachment of incompatible uses.”
P12.01.04: “Prioritize the protection of agriculture and farmlands in Canyon County as an essential part of the County’s economy, identity, and sense of place.”
G12.02.00: “Support farmers and enhance local farmland.”

Canyon County supports preserving agricultural lands, farming activities, and farming-related businesses as long as it is compatible with the surrounding area and appropriate conditions are added to mitigate adverse impacts that affect other land uses and the surrounding community. See the conditions of approval.
</td></tr>
<tr><td>Criteria Met?
Yes</td><td>4</td><td>Will the proposed use be injurious to other property in the immediate vicinity and/or negatively change the essential character of the area?</td></tr>
<tr><td>Analysis</td><td colspan="2">
As conditioned, the proposed use will not be injurious to other property in the immediate vicinity and will not negatively change the essential character of the area.

Summary:
The surrounding land uses within a one-mile radius indicate that the land use in the area primarily is agricultural (Staff Report Exhibits C2.5, C2.7, C2.8, and C4). Although there are some residential properties in the area, the majority have agricultural operations. There are agricultural operations adjacent to the subject property on all sides. A slaughterhouse is allowed in an agricultural zone with a conditional use permit. As conditioned, the proposed use is not anticipated to be injurious to other property within the immediate vicinity, nor negatively change the essential character of the area.

Adjacent Existing Conditions:
<table>
<tr><th>Direction</th><th>Existing Use</th><th>Primary Zone</th><th>Other Zone</th></tr>
<tr><td>N</td><td>Agricultural Operation</td><td>“A”</td><td></td></tr>
<tr><td>S</td><td>Agricultural Operation</td><td>“A”</td><td>“M1”, “C2”, “RR”, and “R1”</td></tr>
<tr><td>E</td><td>Payette County</td><td>Agriculture</td><td>Industrial</td></tr>
<tr><td>W</td><td>Agricultural Operation and Applicant's Primary Residence</td><td>“A”</td><td>“RR”</td></tr>
<tr><td colspan="4">“A” (Agricultural), “R-R” (Rural Residential), “R-1” (Single-Family Residential), “C-1” (Neighborhood Commercial), “C-2” (Service Commercial), “M-1” (Light Industrial), “CR” (Conditional Rezone)</td></tr>
</table>
Surrounding Land Use Cases:
There have been four (4) platted subdivisions approved (Staff Report Exhibit C2.7) in a 1-mile radius from the subject property. All the subdivisions were platted in the early 1900’s. There are no other approved developments in the area.

Character of the Area:
The area is characterized as agricultural. The subject property is adjacent to agricultural operations on all sides. Within 1,000 feet of the subject property, there are 18 properties within Canyon County and Payette County, all located on agriculturally zoned parcels.

Within a 2-mile radius of the subject property, there are two (2) feedlots and one (1) dairy (Staff Report Exhibit C2.8).

The soil classification on the subject property is primarily classified as moderately suited soil (class 4) and least suited soil (class 6) (Staff Report Exhibit C2.10). The proposal utilizes an agriculturally zoned property that doesn’t have the best-suited soils to support livestock production.

Potential Impacts:
The slaughterhouse may impact the surrounding area due to the increase in waste, dust, traffic, odor/smell, and lighting related to the use. Staff has proposed conditions to aid in mitigating these potential effects.
</td></tr>
</table>

	The increase in waste has the potential to impact the surrounding area. The applicant is proposing to contract with a company that will pick up the animal byproduct twice a week to use for animal feed (**Staff Report Exhibits B2.1 and B2.2**). The applicant must meet the waste disposal requirements of the Department of Environmental Quality (DEQ). *See the conditions of approval numbers 1a, 1b, and 1c.* The proposed use may increase the dust levels in the immediate vicinity. Dust shall be controlled in accordance with applicable federal, state, and county laws, ordinances, rules, and regulations pertaining to operations and shall be consistent with Idaho Department of Environmental Quality (DEQ) requirements. To mitigate the potential for dust, the applicant shall submit a dust mitigation plan for staff's review and approval prior to commencement. The applicant must also pave the parking spaces. *See the conditions of approval numbers 9 and 9a.* The proposed use may cause an odor in the immediate vicinity. Canyon County doesn't have any specific code or regulations regarding odors/smells. However, Canyon County's CAFO regulations has further setbacks for animal waste systems if near a residence (CCCO §08-01-12(1)C). Although the request is not for a CAFO, staff is recommending the same setback requirements to mitigate the odor/smell, "The animal waste system shall not be located closer than five hundred feet (500') from an existing residence belonging to someone other than the applicant, or be located and/or operated closer than one hundred feet (100') from the property lines, unless the owner gives written consent to a shorter distance." It appears that the applicant is already meeting this setback requirement with no existing residence located within 500 feet of the proposed use. *See condition number 15.* As conditioned, all exterior lighting, if installed, shall be downward-facing and directed away from surrounding properties. Compliance shall be demonstrated in the building plans submitted as part of the building permit submittal. Review and approval by DSD shall be completed before building permit issuance. *See the condition of approval number 4.* See CCCO §07-07-05(7) for potential traffic impact analysis.	
Criteria Met? **Yes**	**5**	**Will adequate water, sewer, irrigation, drainage and stormwater drainage facilities, and utility systems be provided to accommodate the use?**
Analysis	The project will have adequate water, sewer, irrigation, drainage, and stormwater drainage facilities, and utility systems to accommodate the proposed use based on the analysis contained herein. **Water:** The property appears to have adequate water via an individual well. There are no additional wells proposed to serve the proposed slaughterhouse (**Staff Report Exhibit B4**). Idaho Department of Water Rights (IDWR) commented on April 7, 2026, stating that the proposed use would be able to be supplied by the existing domestic well as long as water does not exceed 2,500 gallons per day. If the use exceeds the maximum amount allowed, the applicant will need to obtain a commercial water right. The area is open for new water rights, and after conducting a preliminary check, Idaho Department of Water Rights (IDWR) does not see any areas of concern (**Staff Report Exhibit E4**). The existing water uses are anticipated to provide adequate water for the proposed use. *See the condition of approval number 13.* **Sewer:** The applicant is proposing to have one restroom on-site for customer and employee use (**Staff Report Exhibit B2.2**). Comment from Southwest District Health on April 22, 2026, advised that a preliminary subsurface sewage disposal permit has been issued and is consistent with the total wastewater design flow specified in the approved letter of intended use (**Staff Report Exhibit E8**). The pre-development notes specified that the letter of intended use was submitted and approved by Southwest District Health and Idaho Department of Environmental Quality (DEQ). It was also identified that the originally proposed drain field location encroaches into an area subject to vehicle traffic, which may result in soil compaction and compromised system performance. New test holes will be required in an alternate location to evaluate site suitability for a revised drain field area that avoids vehicle traffic impacts (**Staff Report Exhibit E8.1**). The approved preliminary septic permit can be seen in **Staff Report Exhibit E8.2**. *See the condition of approval number 10.*	

	Pre-Development Notes from Southwest District Health advises that the proposed drain field area must maintain a minimum setback of at least 50 feet from the canal (**Staff Report Exhibit E8.1**). **Waste Disposal:** The applicant will contract with the business "Darling", which provides a container for the meat by-products (including bones). "Darling" will pick up the animal by-product twice a week to use for animal food and other products (**Staff Report Exhibits B2.1, B2.2, and B2.3**). The applicant will recycle the manure into his pasture, which will continue to be used for the property owner's livestock (**Staff Report Exhibit B2.3**). The preliminary septic permit for the slaughterhouse that was issued and approved by Southwest District Health and the Department of Environmental Quality accounted for the blood waste (**Staff Report Exhibit E8.3**). **Irrigation:** Agency notice was sent out to Farmers Cooperative Ditch Company and Black Canyon Irrigation District on November 14, 2025, and April 16, 2026. A comment letter received from Farmers Cooperative Ditch Company on April 8, 2026, advised that the proposed use should not impact the water quality or surface runoff, and requests that there are safeguards in place for animal waste to not run into the canal (**Staff Report Exhibit E5**). No comments were received from Black Canyon Irrigation District. *Condition number 5* ensures the applicant shall not impede, disrupt, or disturb the existing irrigation structure without approval from the irrigation district. *See the conditions of approval numbers 1a, 1b, and 1c* to manage the concern of animal waste running into the canal. **Stormwater drainage facilities:** As conditioned, stormwater will be retained onsite. *See the condition of approval number 12.* **Utility Systems:** Utility agencies, including Idaho Power, Intermountain Gas, CenturyLink, and Ziply, were notified of the application on November 14, 2025, and April 16, 2026. No agency comments were provided by those services at the time the staff report was written. It is anticipated that the applicant will be able to work with utility providers to gain any additional utilities needed.	
Criteria Met? **Yes**	**6**	**Does legal access to the subject property for the development exist or will it exist at the time of development?**
Analysis	The subject property will have legal access at the time of the development. Access to the facility is proposed to utilize Hwy 95 (**Staff Report Exhibit B7**). The subject property has an old farm field approach. The approach will not meet the current standards of Idaho Transportation Department. Therefore, a new access point will be required (**Staff Report Exhibit E2.2**). According to a comment letter received from the Idaho Transportation Department, an approach permit application is required and access is required to be constructed to meet the current specs of a commercial two-way approach (**Staff Report Exhibit E2**). *See condition number 3.*	
Criteria Met? **Yes**	**7**	**Will there be undue interference with existing or future traffic patterns?**
Analysis	Undue interference with the existing or future traffic patterns is not anticipated. Any potential impact will be reviewed by Idaho Department of Transportation (ITD). It is anticipated that there will be a maximum of eight (8) employees and approximately 20 vehicles a week (**Staff Report Exhibits B2.2 and B4**). The subject property takes access from Hwy 95, which is serviced by the Idaho Transportation Department (ITD). ITD's comment received on April 6, 2026, states that the proposal is for a relatively small operation and does not expect to have any traffic concerns related to the proposal. ITD's trip generation estimates approximately 16 vehicles during AM peak hours and 13 vehicles during PM peak hours (**Staff Report Exhibit E2.1)**. *See condition number 3.* Based on the traffic information from ITD, the proposed use is not anticipated to cause any undue impact to the existing or future traffic patterns.	

Criteria Met?		
Yes	8	**Will essential services be provided to accommodate the use including, but not limited to, school facilities, police and fire protection, emergency medical services, irrigation facilities, and will the services be negatively impacted by such use or require additional public funding in order to meet the needs created by the requested use?**
Analysis	Essential services will be provided to accommodate the use, including, but not limited to, school facilities, police and fire protection, emergency medical services, and irrigation facilities. The services will not be negatively impacted by such use or require additional public funding in order to meet the needs created by the requested use. **School Facilities:** Parcel R39357012 is serviced by the Parma School District. It is not anticipated that any impact or accommodations will be needed for the proposed use. Agency comments were sent out on November 14, 2025, and April 16, 2026. No comments were received by the school district. **Police and Fire Protection:** Parcel R39357012 is under the jurisdiction of the Parma Fire District. Parma Fire District is required to provide services to the parcel. As conditioned, the applicant shall comply with all Fire District requirements per State adopted IFC, and as evidenced by review and approval documentation from the applicable fire district prior to issuance of a certificate of occupancy and commencement of activities on the site. All development shall comply with the 2018 International Fire Code and codes set forth by Canyon County. *See condition number 11.* Agency notice was sent on November 14, 2025, and April 16, 2026. Parma Fire District provided comment on May 4, 2026, advising that the response time to the subject property is approximately 5 minutes (**Staff Report Exhibit E11**). No comment was received from the Canyon County Sheriff's Department. **Emergency Medical Services:** Emergency Medical Services are provided to the property. Canyon County Paramedics/EMT and Canyon County's Emergency Management were notified of the application on November 14, 2025, and April 16, 2026. Canyon County Paramedics/EMT provided their response times to the subject property on May 1, 2026. The response times vary from 25.02 minutes, 27.10 minutes, and 28.30 minutes. It was advised that the Parma Fire District would have a faster response time to the subject property (**Staff Report Exhibit E10**). No comment was received from Canyon County's Emergency Management. Overall, the use is not anticipated to be significant enough to cause a negative impact or require additional public funding. **Irrigation Facilities:** Agency notice was sent out to Farmers Cooperative Ditch Company and Black Canyon Irrigation District on November 14, 2025, and April 16, 2026. A comment letter received from Farmers Cooperative Ditch Company on April 8, 2026, advised that the proposed use should not impact the water quality or surface runoff, and requests that there are safeguards in place for animal waste to not run into the canal (**Staff Report Exhibit E5**). No comments were received from Black Canyon Irrigation District. *Condition number 5* ensures the applicant shall not impede, disrupt, or disturb the existing irrigation structure without approval from the irrigation district. *See the conditions of approval numbers 1a, 1b, and 1c* to manage the concern of animal waste running into the canal.	

Order

Based upon the Findings of Fact, Conclusions of Law and Order contained herein, the Planning and Zoning Commission **approves** Case # CU2025-0031, a conditional use permit for a slaughterhouse with retail sales as an accessory use, subject to the following conditions as enumerated:

Conditions of Approval

1. The development shall comply with all applicable federal, state, and county laws, ordinances, rules, and regulations that pertain to the subject property and the proposed use.
    a. Water (including surface, groundwater, and stormwater) shall be discharged in accordance with state, federal, and local standards and/or regulations.
    b. The operator shall dispose of waste in a manner that does not contribute to potential environmental and water contamination in and around the subject property.
    c. The applicant shall coordinate with the Department of Environmental Quality (DEQ) to manage on-site waste products and disposal. Evidence shall be a letter of review and approval from DEQ, provided prior to commencement of use (**Staff Report Exhibit E1**).
    d. The applicant shall meet Canyon County's GIS Department requirements prior to beginning operations (**Staff Report Exhibit E6**).
2. The applicant shall obtain a commercial building permit for the slaughterhouse prior to commencement of use.
    a. The applicant shall appropriately permit the agriculture (AG) building within **180 days of the approval of the Conditional Use Permit** (**Staff Report Exhibit E7**).
    b. Development on slopes 15% or greater, as shown in the USGS Map (**Staff Report Exhibit C2.14**), requires a preliminary engineered grading and drainage plan for any development (grading, road construction, and structures) to be submitted prior to building issuance in compliance with §07-17-33(1)C. Applicable regulations and standards of the stated code shall be determined by the County Engineer, and the plan shall be reviewed and approved by the County Engineer. Any review fees shall be paid by the applicant prior to building permit issuance. A final engineered grading and drainage shall be submitted prior to the certificate of occupancy.
3. The applicant shall comply with applicable Idaho Department of Transportation (ITD) requirements prior to operations (**Staff Report Exhibit E2**).
    a. An approved approach permit shall be obtained prior to commencement of the use for the proposed access, as evidenced by the applicant providing Development Services with an approved Idaho Department of Transportation (ITD) document indicating the completion of improvements.
4. All exterior lighting, if installed, shall be downward-facing and directed away from surrounding properties. Compliance shall be demonstrated in the building plans submitted as part of the building permit submittal via an exterior lighting plan. Review and approval by DSD shall be completed before building permit issuance.
5. The applicant shall not impede, disrupt, or otherwise disturb the existing irrigation structures on and adjacent to the subject property and easement without written approval from the irrigation district with jurisdiction.
6. Signage shall meet CCCO §07-10-13 requirements and shall not exceed 32 sq. feet and 10 feet in height unless an additional sign permit is applied for and approved by the Director. If it exceeds 6 ft in height, a building permit is required.
7. The proposed development shall be in general conformance with the applicant's site plan and letter of intent (**Staff Report Exhibits B2, B2.1, and B3**).
    a. Employees' vehicles shall be parked on-site and not on a public or private road. Business vehicles shall be operable and parked on site, not on a public or private road.
    b. The proposed retail sales shall stay as an accessory use to the slaughterhouse and shall not exceed 400 sq. ft in size.
    c. The applicant must have no less than 10 parking spaces on-site in accordance with CCCO Section 07-13-03.

d. The hours of operation shall be Monday through Saturday, 7 am – 5 pm (**Exhibit B4**).

8. This conditional use permit must follow land use time limitation as stated in CCCO 07-07-23: "When a conditional use permit is granted, the land use or construction of its facility proposed in the application must have commenced within three (3) years of the date of the final decision by the presiding party or a court of appropriate jurisdiction. The improvements for the approved use must be completed within five (5) years of the same date.
9. A dust mitigation plan shall be provided prior to commencement of use to the Development Services Department. Dust shall be controlled in accordance with applicable federal, state, and county laws, ordinances, rules, and regulations pertaining to operations and shall be consistent with Idaho Department of Environmental Quality (DEQ) requirements.
    a. The applicant shall pave the parking area (**Staff Report Exhibit B2.2**).
10. The applicant shall meet all applicable Southwest District Health (SWDH) requirements for the proposed use. Evidence shall be a letter of review and approval from SWDH, provided prior to commencement of use (**Staff Report Exhibit E8.1**).
    a. The applicant shall obtain the required food permits prior to beginning operations unless waived (**Staff Report Exhibit E9.1**).
11. The applicant shall comply with all fire district requirements per State adopted IFC and as evidenced by review and approval documentation from Parma Fire District prior to commencement of use.
12. The applicant shall retain stormwater drainage onsite.
13. The applicant shall obtain water rights for the proposed use through the Idaho Department of Water Rights (IDWR) if the proposed use exceeds 2,500 gallons per day (**Staff Report Exhibit E4**).
14. The applicant shall meet all applicable U.S. Department of Agriculture (USDA) requirements for the proposed use. Evidence shall be a letter of review and approval from USDA, provided prior to commencement of use (**Staff Report Exhibit E9.2**).
15. Waste System Setbacks:
    a. The animal waste system shall not be located closer than five hundred feet (500') from an existing residence belonging to someone other than the applicant, or be located and/or operated closer than one hundred feet (100') from the property lines, unless the other owner gives written consent to a shorter distance.
    b. No animal waste system shall be located closer than one hundred feet (100') from a domestic or irrigation well.
    c. No animal waste system shall be located closer than one hundred feet (100') from a public right of way.
16. The conditional use for the slaughterhouse shall be limited to Lucus Hansen and family. Should ownership of parcel R39357012 change from Lucus Hansen or an immediate family member, the conditional use permit for a slaughterhouse shall terminate.

DATED this _____ day of _____, 2026.

PLANNING AND ZONING COMMISSION
CANYON COUNTY, IDAHO

_____
Robert Sturgill, Chairman

State of Idaho)

SS

County of Canyon County)

On this _____day of _____, in the year 2026, before me_____, a notary public, personally appeared _____, personally known to me to be the person whose name is subscribed to the within instrument, and acknowledged to me that he (she) executed the same.

Notary: _____

My Commission Expires: _____

Exhibit B:

EXHIBIT B

Application Packet & Supporting Materials

Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 21, 2026

Exhibit B1:

CONDITIONAL USE PERMIT
PUBLIC HEARING - APPLICATION

PROPERTY OWNER	OWNER NAME: Lucus Hansen	
	MAILING ADDRESS: 32501 Hwy 95 Parma	
	PHONE [redacted]	EMAIL: [redacted]

I consent to this application and allow DSD staff / Commissioners to enter the property for site inspections. If the owner(s) is a business entity, please include business documents, including those that indicate the person(s) who are eligible to sign.

Signature: _____ *Date:* 10/15/25

APPLICANT: IF DIFFERING FROM THE PROPERTY OWNER	APPLICANT NAME:	
	COMPANY NAME:	
	MAILING ADDRESS:	
	PHONE:	EMAIL:

SITE INFO	STREET ADDRESS: Hwy 95 Parma	
	PARCEL NUMBER: R39357012	
	PARCEL SIZE: 11 acres	
	REQUESTED USE: Slaughter house / Butcher shop	
	FLOOD ZONE (YES/NO)	ZONING DISTRICT: A

FOR DSD STAFF COMPLETION ONLY:

CASE NUMBER	CU2025-0031	DATE RECEIVED:	11/10/25
RECEIVED BY:	MG	APPLICATION FEE: $1,600	(CK) MO CC CASH

CANYON COUNTY DEVELOPMENT SERVICES DEPARTMENT
111 North 11th Avenue, #310, Caldwell, ID 83605
zoninginfo@canyoncounty.id.gov - Phone: 208-402-4164
Revised 3/29/23

Exhibit B2:

To whom it may concerne,

I'm writing a letter of intent to propose a custom butcher business/slaughter house with retail sales. We will accept animals from customers for processing. We will have an average of 5 people working. Hours of operation will be 7 a.m. to 5 p.m. Monday-Friday.
There should be no potential impacts to the property.

We will provide utilities such as power, private well, septic system, and necessary storm drainage.

Access will be off of Hwy 95 in Parma, with no traffic pattern disruption.

Exhibit B2.1:

Archived: Tuesday, April 28, 2026 2:38:09 PM
From: lucus hansen
Mail received time: Thu, 5 Feb 2026 01:25:30
Sent: Wed, 4 Feb 2026 18:25:08
To: Amber Lewter
Subject: [External] Re: CU2025-0031
Importance: Normal
Sensitivity: None
Attachments:
image001.png

Parking will be in front of the building
We will be slaughtering beef pigs mostly
The goal is to get up to 10 beef a week to slaughter
We will contract with a company that comes by and picks up the waste for dog food ect.
The pen will be behind the building i have a big pasture behind it and will build a holding pen.
Thanks
Lucus
208-919-1056

On Wed, Feb 4, 2026, 1:11 'a0PM Amber Lewter <Amber.Lewter@canyoncounty.id.gov> wrote:

> Hello Lucus,
>
> Thank you for providing me with the Septic Permit. I have a few follow-up questions below. Please answer as soon as possible.
>
> - Where will the parking be located?
> - Where will the pen to hold the animals be located, and how large will it be?
> - How many animals will you hold at a time for slaughter?
> - What kind of animals will you be providing this service to?
> - Will there be waste?
>   - What is your waste disposal plan?
>   - How will you be distributing the waste?
>
> Thank you,

Exhibit B2.2:

Archived: Tuesday, April 28, 2026 2:38:16 PM
From: lucus hansen
Mail received time: Tue, 7 Apr 2026 00:32:03
Sent: Mon, 6 Apr 2026 18:31:39
To: Amber Lewter
Subject: [External] Re: CU2025-0031
Importance: Normal
Sensitivity: None
Attachments:
image001.png

Hello,
I am planning on 1 bathroom+1 break room
I plan to pave the parking lot
Probably around 5-6 parking spots
They pick up animal products 2 times a week
Retail space might be 100 sft
I anticipate probably 20 cars a week

Anymore questions let me know
Thanks Lucus

On Mon, Apr 6, 2026, 2:21 'a0PM Amber Lewter <Amber.Lewter@canyoncounty.id.gov> wrote:

> Hello Lucus,
>
> I have a few follow-up questions. I may have further questions within the next couple of weeks as well. Please answer these as quickly as possible.
>
> Will you have restrooms or porta-potties? How many?
>
> How many parking spaces? Will the parking be gravel, paved, or dirt?
>
> How often will the company for the animal food pick up the waste?
>
> How much traffic do you anticipate in a day/week?

How large will the retail portion of the proposal be?

Thank you,

Amber Lewter

Associate Planner

Canyon County Development Services Department

111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631

Email: amber.lewter@canyoncounty.id.gov

Website: www.canyoncounty.id.gov

Development Services Department (DSD)

Public office hours

Monday, Tuesday, Thursday and Friday

8am – 5pm

Wednesday

1pm – 5pm

**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

Exhibit B2.3:

Archived: Thursday, April 30, 2026 9:43:49 AM
From: Amber Lewter
Sent: Thursday, April 30, 2026 9:41:54 AM
To: [redacted]
Subject: CU2025-0031
Importance: Normal
Sensitivity: None

Hello Lucus,

I wanted to provide you with a recap of the conversation we had on April 29, 2026.

- It was discussed that you have a special septic system to account for blood waste.
- You will be working with Darling for waste management. Darling will provide a container to place the meat by-products in (including the bones), and they will come collect the meat by-products twice a week.
- When inquiring about the manure. It was explained that there shouldn't be much manure because the animals are dropped off, placed in the pen, and slaughtered the next day. The manure that is there will be placed in a pile and used in your pasture. This is the same process you do with your livestock on the property.
- You will continue to have your livestock.

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov
Website: www.canyoncounty.id.gov

Development Services Department (DSD)
Public office hours
Monday, Tuesday, Thursday and Friday
8am – 5pm
Wednesday
1pm – 5pm
**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

American CONSTRUCTION SUPPLY & RENTAL

JOB _____ **Exhibit B3:**

SHEET NO. _____

CALCULATED BY _____ DATE _____

CHECKED BY _____ DATE _____

SCALE _____

10 LOCATIONS TO SERVE YOU:

SPECIAL PROJECTS DIVISION
601 N 36TH ST
NAMPA, ID 83687
208-467-4591

WESTERN IDAHO & EASTERN OREGON LOCATIONS
3500 GARRITY BLVD
NAMPA, ID 83687
208-467-4231

1740 SE 5TH AVE
ONTARIO, OR 97914
541-889-8985

EASTERN IDAHO LOCATIONS
195 EASTLAND DR
TWIN FALLS, ID 83301
208-733-2007

3685 US HWY 30 WEST
POCATELLO, ID 83201
208-478-5117

EQUIPMENT DIVISION
520 N 36TH ST
NAMPA, ID 83687
208-844-7118

4525 MARKET ST
BOISE, ID 83705
208-336-8080

13850 HWY 55 S
MCCALL, ID 83638
208-634-0150

2092 N YELLOWSTONE HWY
IDAHO FALLS, ID 83401
208-523-0667

868 JET STREAM DR
REXBURG, ID 83440
208-356-4429

- Forming
- Shoring
- Engineering
- Tilt-Up
- Gomaco Paving & Curb Machines
- Paving Materials
- Finishing Equipment
- Husqvarna Concrete Saws
- Somero Laser Screeds
- Compaction Equipment
- Equipment Rental
- Equipment Service & Repair
- Diamond Blades
- Formwork Plywood
- Insulation Board
- Hilti Power Tools
- Trench Drain
- Vibrators
- Concrete Repair
- Curing Compounds
- Epoxy
- Hammer Drills
- Breakers
- Forming Hardware
- Anchor Bolts
- Concrete Tools
- Column Tube
- Power Trowels
- Decorative Concrete Supplies
- Lasers
- Levels
- Waterproofing Material
- Rebar Fabrication
- Form Oil




Exhibit B4:

LAND USE WORKSHEET

PLEASE CHECK ALL THAT APPLY TO YOUR REQUEST:

GENERAL INFORMATION

1. **DOMESTIC WATER:** ☒ Individual Domestic Well ☐ Centralized Public Water System ☐ City

   ☐ N/A – Explain why this is not applicable: _____

   ☐ How many Individual Domestic Wells are proposed? 1

2. **SEWER (Wastewater)** ☒ Individual Septic ☐ Centralized Sewer system

   ☐ N/A – Explain why this is not applicable: _____

3. **IRRIGATION WATER PROVIDED VIA:**

   ☒ Surface ☐ Irrigation Well ☐ None

4. **IF IRRIGATED, PROPOSED IRRIGATION:**

   ☒ Pressurized ☐ Gravity

5. **ACCESS:**

   ☒ Frontage ☐ Easement Easement width_____ Inst. # _____

6. **INTERNAL ROADS:**

   ☐ Public ☐ Private Road User's Maintenance Agreement Inst #_____

7. **FENCING** ☐ Fencing will be provided (Please show location on site plan)

   Type: _____ Height: _____

8. **STORMWATER:** ☐ Retained on site ☐ Swales ☐ Ponds ☐ Borrow Ditches

   ☐ Other: _____

9. **SOURCES OF SURFACE WATER ON OR NEARBY PROPERTY:** (i.e. creeks, ditches, canals, lake)

   Canal Farmers coop Canal

RESIDENTIAL USES

1. **NUMBER OF LOTS REQUESTED:**

☐ Residential _____ ☐ Commercial _____ ☐ Industrial _____

☐ Common _____ ☐ Non-Buildable _____

2. **FIRE SUPPRESSION:**

☐ Water supply source: _____

3. **INCLUDED IN YOUR PROPOSED PLAN?**

☐ Sidewalks ☐ Curbs ☐ Gutters ☐ Street Lights ☐ None

NON-RESIDENTIAL USES

1. **SPECIFIC USE:** Slaughterhouse

2. **DAYS AND HOURS OF OPERATION:**

☒ Monday 7 to 5

☒ Tuesday 7 to 5

☒ Wednesday 7 to 5

☒ Thursday 7 to 5

☒ Friday 7 to 5

☒ Saturday 7 to 5

☐ Sunday _____ to _____

3. **WILL YOU HAVE EMPLOYEES?** ☒ Yes If so, how many? 3 - 8 ☐ No

4. **WILL YOU HAVE A SIGN?** ☒ Yes ☐ No ☐ Lighted ☒ Non-Lighted

Height: 10 ft Width: 8 ft. Height above ground: _____ ft

What type of sign: _____ Wall X Freestanding _____ Other

5. **PARKING AND LOADING:**

How many parking spaces? 9

Is there is a loading or unloading area? Yes

ANIMAL CARE-RELATED USES

1. **MAXIMUM NUMBER OF ANIMALS:** _____

2. **HOW WILL ANIMALS BE HOUSED AT THE LOCATION?**

   ☐ Building ☐ Kennel ☐ Individual Housing ☐ Other _____

3. **HOW DO YOU PROPOSE TO MITIGATE NOISE?**

   ☐ Building ☐ Enclosure ☐ Barrier/Berm ☐ Bark Collars

4. **ANIMAL WASTE DISPOSAL**

   ☐ Individual Domestic Septic System ☐ Animal Waste Only Septic System

   ☐ Other: _____

Exhibit B5:

Dear Neighbor,

We are in the process of applying for a special use permit. We are required to hold a Neighborhood meeting. We will be proposing a butcher/slaughter house. We will be answering any questions you may have.

Adress: TBD Hwy 95, Parma, ID 83660

West of Hwy 95 between Ward LN and Grandview.

Date: November 6, 2025

Time: 7 PM

Thanks

Lucus Hansen

NEIGHBORHOOD MEETING SIGN-UP

CANYON COUNTY DEVELOPMENT SERVICES DEPARTMENT
111 North 11th Avenue, #310, Caldwell, ID 83605
zoninginfo@canyoncounty.id.gov Phone: 208-402-4164

NEIGHBORHOOD MEETING SIGN UP SHEET

CANYON COUNTY ZONING ORDINANCE §07-01-15

Applicants shall conduct a neighborhood meeting for any proposed comprehensive plan amendment, zoning map amendment (rezone), subdivision, variance, conditional use, zoning ordinance map amendment, or other requests requiring a public hearing.

SITE INFORMATION

Site Address: TBD Hwy 95	Parcel Number: R 3935010	
City: Parma, ID 83660	State: ID	ZIP Code: 83660
Notices Mailed Date: 10/21/25	Number of Acres: 11	Current Zoning:
Description of the Request: Permit		

APPLICANT / REPRESENTATIVE INFORMATION

Contact Name: Lucus Hanson		
Company Name:		
Current address: 35501 Hwy 95		
City: Parma, ID.	State: ID.	ZIP Code: 83660
Phone:	Cell: [redacted]	Fax:
Email: [redacted]		

MEETING INFORMATION

DATE OF MEETING: 11/6/25	MEETING LOCATION: Hwy 95 crossroad Grandview & Ward Rd.
MEETING START TIME: 7:00 pm	MEETING END TIME: 7:30 pm
ATTENDEES: 0	

NAME (PLEASE PRINT)	SIGNATURE:	ADDRESS:
1.		
2. No one showed up		
3.		
4.		
5.		
6.		
7.		
8.		
9.		

10.
11.

12.
13.
14.
15.
16.
17.
18.
19.
20.

NEIGHBORHOOD MEETING CERTIFICATION:

I certify that a neighborhood meeting was conducted at the time and location noted on this form and in accordance with Canyon County Zoning Ordinance § 07-01-15.

APPLICANT/REPRESENTATIVE (Please print):

Lucas Hanson

APPLICANT/REPRESENTATIVE (Signature):

DATE: 11 / 9 / 25

Exhibit B6:

AGENCY ACKNOWLEDGMENT

Date: 10/14/25
Applicant: R39357012 Lucas Hansen
Parcel Number: R39357012
Site Address: TBT Hwy 95

OFFICIAL USE ONLY BELOW THIS LINE – ACKNOWLEDGMENT ACTION:

Southwest District Health:
☐ Applicant submitted/met for official review.
Date: 10/1/25 Signed: RLEHS
Authorized Southwest District Health Representative
(This signature does not guarantee project or permit approval)

Fire District: District: Parma Fire
☑ Applicant submitted/met for official review.
Date: 9/24/25 Signed:
Authorized Fire District Representative
(This signature does not guarantee project or permit approval)

Highway District: District: Notus-Parma Highway District
☑ Applicant submitted/met for official review.
Date: 9-29-25 Signed:
Authorized Highway District Representative
(This signature does not guarantee project or permit approval)

Irrigation District: District:
☐ Applicant submitted/met for official review.
Date: Signed:
Authorized Irrigation Representative
(This signature does not guarantee project or permit approval)

Melissa
Area of City Impact: City:
☐ Applicant submitted/met for official review.
Date: Signed:
Authorized AOCI Representative
(This signature does not guarantee project or permit approval)

Received by Canyon County Development Services:

Date: Signed:
Canyon County Development Services Staff

DISCLAIMER: THIS ACKNOWLEDGMENT IS ONLY VALID SIX MONTHS FROM THE DATE ISSUED

AGENCY ACKNOWLEDGMENT

Date:
Applicant:
Parcel Number:
Site Address:

OFFICIAL USE ONLY BELOW THIS LINE – ACKNOWLEDGMENT ACTION:

Southwest District Health:
☐ Applicant submitted/met for official review.

Date: _____ Signed: _____
Authorized Southwest District Health Representative
(This signature does not guarantee project or permit approval)

Fire District: District: Parma Fire
☒ Applicant submitted/met for official review.

Date: 9/24/25 Signed: _____
Authorized Fire District Representative
(This signature does not guarantee project or permit approval)

Highway District: District: _____
☐ Applicant submitted/met for official review.

Date: _____ Signed: _____
Authorized Highway District Representative
(This signature does not guarantee project or permit approval)

Irrigation District: District: Black Canyon Irrigation
☒ Applicant submitted/met for official review.

Date: 9-29-25 Signed: _____
Authorized Irrigation Representative
(This signature does not guarantee project or permit approval)

Melissa
Area of City Impact: City: _____
☐ Applicant submitted/met for official review.

Date: _____ Signed: _____
Authorized AOCI Representative
(This signature does not guarantee project or permit approval)

Received by Canyon County Development Services:

Date: _____ Signed: _____
Canyon County Development Services Staff

DISCLAIMER: THIS ACKNOWLEDGMENT IS ONLY VALID SIX MONTHS FROM THE DATE ISSUED

Exhibit B7:



Exhibit B8:



HIGH WATER MARK
High Water Mark Engineering
3313 W Cherry Lane #1102
Meridian Idaho 83642
(208) 990-1848

N

0 20 40 80 120 Feet

PRELIMINARY SITE MAP

5/11/2026

Butcher Shop = approx. 6,000 sq ft

Exhibit C:

EXHIBIT C

Supplemental Documents

Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 21, 2026

CANYON COUNTY DEVELOPMENT SERVICES MAKES NO WARRANTY WITH RESPE
ACCURACY, COMPLETENESS, OR USEFULNESS OF THIS PARCEL INFORMATIO

Exhibit C1:

R39357012 PARCEL INFORMATION REPORT

4/28/2026 2:35:24 PM

PARCEL NUMBER:	R39357012
OWNER NAME:	HANSENS HOLDINGS LLC
CO-OWNER:	
MAILING ADDRESS:	32501 HWY 95 PARMA ID 83660
SITE ADDRESS:	0 HWY 95
TAX CODE:	0490000
TWP:	6N **RNG:** 5W **SEC:** 20 **QUARTER:** NE
ACRES:	11.30
HOME OWNERS EXEMPTION:	No
AG-EXEMPT:	No
DRAIN DISTRICT:	NOT In Drain Dist
ZONING DESCRIPTION:	AG / AGRICULTURE
HIGHWAY DISTRICT:	NOTUS-PARMA HWY #2
FIRE DISTRICT:	PARMA FIRE
SCHOOL DISTRICT:	PARMA SCHOOL DIST #137
IMPACT AREA:	NOT In Impact Area
FUTURE LAND USE 2011-2022 :	AG
FLU Overlay Zone Desc 2030:	INTENSIVE AGRICULTURE OVERLAY / SCENIC BYWAY BUFFER
FLU RR Zone Desc 2030:	
FUTURE LAND USE 2030:	AGRICULTURE
IRRIGATION DISTRICT:	BLACK CANYON IRRIGATION DIST / FARMERS COOPERATIVE DITCH CO
FEMA FLOOD ZONE:	X **FLOODWAY:** NOT In FLOODWAY **FIRM PANEL:** 16027C0075G
WETLAND:	Freshwater Emergent Wetland / Riverine
NITRATE PRIORITY:	NO Nitrate Prio
FUNCTIONAL Classification:	NOT In COLLECTOR
INSTRUMENT NO. :	2024025747
SCENIC BYWAY:	YES
LEGAL DESCRIPTION:	20-6N-5W NE TX 20205 IN E1/2 OF NE
PLATTED SUBDIVISION:	
SMALL CITY ZONING:	
SMALL CITY ZONING TYPE:	

DISCLAIMER:

1. FEMA FLOOD ZONE REFERS TO THE DESIGNATED FEMA FLOOD AREAS. POSSIBLY ONE (1) OF SEVERAL ZONES - SEE FIRM PANEL NUMBER.
2. THIS FORM DOES NOT CALCULATE DATA FOR PARCELS INSIDE CITY LIMITS SO WATCH YOURSELVES.
3. WETLANDS CLASSIFICATION WILL POPULATE IF "ANY" PORTION OF SAID PARCEL CONTAINS A DELINEATED WETLAND.
4. COLLECTORS AND ARTERIALS ARE BASED ON THE SHERRIFS CENTERLINE WITH AN ADDITIONAL 100 FOOT BUFFER.

CANYON COUNTY ASSUMES NO LIABILITY FOR DIRECT, INDIRECT, SPECIAL, OR CONSEQUENTIAL DAMAGES RESULTING FROM THE USE OR MISUSE OF THIS PARCEL INFORMATION TOOL OR ANY OF THE INFORMATION CONTAINED HEREIN.

Exhibit C2:

EXHIBIT C2

Case Maps/Reports


Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 21, 2026

Canyon County, ID Web Map

Exhibit C2.1:



11/10/2025, 2:13:25 PM

Multiple Parcel Search _Query result

Hydro_NHDFlowline

CanyonCountyRoads

Hwy

Roads

County Boundary

Current Impact Area

City Limits

Sections

Imagery_2025_3in

Red: Band_1

Green: Band_2

1:9,028


0 0.05 0.1 0.2 mi

0 0.07 0.15 0.3 km

Bureau of Land Management, State of Oregon, State of Oregon DOT, State of Oregon GEO, Esri Canada, Esri, HERE, Garmin, INCREMENT P, Intermap, USGS, METI/NASA, EPA, USDA

Canyon County, ID

Bureau of Land Management, State of Oregon, State of Oregon DOT, State of Oregon GEO, Esri Canada, Esri, HERE, Garmin, INCREMENT P, Intermap, USGS, METI/NASA, EPA, USDA | City of Nampa |




City_Limits
Wetlands

0 0.25 0.5 Miles

IMAGES WERE FLOWN IN THE FALL OF 2024.

Exhibit C2.3:

Hansen
FEMA Small Air Photo




Legend


- SUBJECT_PROPERTY
- TAXLOTS
- WETLANDS
- A
- AE
- X

400 0 400 Feet

Exhibit C2.4:

Hansen
Small Vicinity Map









Exhibit C2.5:


Hansen
Zoning & Classification Map



CANYON COUNTY, IDAHO — DEVELOPMENT SERVICES — GEOGRAPHICAL INFORMATION SYSTEMS


- RR
- CR-RR
- R1
- CR-R1
- R2
- C
- C1
- CR-C1
- C2
- CR-C2
- M1
- CR-M1
- M2
- AG
- INTERSTATE
- OTHER FREEWAY/ EXPRESSWAY
- PROPOSED OTHER FREEWAY/ EXPRESSWAY
- PRINCIPAL ARTERIAL
- PROPOSED PRINCIPAL ARTERIAL
- MINOR ARTERIAL
- PROPOSED MINOR ARTERIAL
- COLLECTOR
- PROPOSED COLLECTOR

0 0.25 0.5 Miles


Exhibit C2.6:
Hansen
Case Map
CALLE DE LA
1ST LN
LOCKER AVE
RIVER BLUFF RD
SUNSET VIEW RD
ISLAND RD
UNITY LN
ROCKY RD
GRANDVIEW RD
GRANDVIEW AVE
APPLE VALLEY RD
FISK RD
HWY 95
SUBJECT PROPERTY
WARD LN
NICHOL LN
COACH RD
ADA LN
NOB LN
APPLE WAY
SLATE LN
DOT LN
PEARL RD
WINECUP LN
STUBB LN
HURTZ RD
RUSSIAN OLIVE LN
HURTZ LN
PARMA RD
LOUISE LN
SHEEP CAMP PASS LN
VALERIE LN
CIRCLE DR
OLD FORT BOISE RD
Year
2020
2021
2022
2023
2024
2025
0
0.5
1
Miles

CASE SUMMARY

ID	CASENUM	REQUEST	CASENAME	FINALDECIS


Exhibit C2.7:
Hansen
Subdivision Map
1ST LN
HWY 95
RIVER BLUFF RD
4
ISLAND RD
ROCKY RD
2
3
GRANDVIEW RD
GRANDVIEW AVE
SUBJECT PROPERTY
FISK RD
1
2
NICHOL LN
ADA LN
WARD LN
APPLE VALLEY RD
NOB LN
PEARL RD
DOT LN
STUBB LN
2
HURTZ RD
HURTZ LN
PARMA RD
LOUISE LN
VALERIE LN
CIRCLE DR
3
OLD FORT BOISE RD
SUBDIVISIONS
Plat Type,Plat Status
Preliminary,Approved
Preliminary,Pending
MOBILE HOME PARKS
0
0.25
0.5
Miles

SUBDIVISION & LOT REPORT

NUMBER OF SUBS	ACRES IN SUB	NUMBER OF LOTS	AVERAGE LOT SIZE
4	1934.69	224	8.64

NUMBER OF SUBS IN PLATTING	ACRES IN SUB	NUMBER OF LOTS	AVERAGE LOT SIZE
0			

NUMBER OF LOTS NOTIFIED	AVERAGE	MEDIAN	MINIMUM	MAXIMUM
9	27.78	18.47	2.21	75.79

NUMBER OF MOBILE HOME PARKS	ACRES IN MHP	NUMBER OF SITES	AVG HOMES PER ACRE	MAXIMUM
0				

PLATTED SUBDIVISIONS

SUBDIVISION NAME	Label	LOCATION	ACRES	NO. OF LOTS	AVERAGE LOT SIZE	CITY OF...	Year
APPLE VALLEY LAND CO	1	6N5W20	283.16	11	25.74	COUNTY (Canyon)	1916
IDAHO INVESTMENT CO	2	6N5W29	699.53	109	6.42	COUNTY (Canyon)	1916
IDAHO LAND CO	3	6N5W18	670.68	58	11.56	COUNTY (Canyon)	1909
ORCHARD TRACT OF THE IDAHO LAND COMPANY	4	6N5W17	281.33	46	6.12	COUNTY (Canyon)	1909

SUBDIVISIONS IN PLATTING

SUBDIVISION NAME	ACRES	NO. OF LOTS	AVERAGE LOT SIZE

MOBILE HOME & RV PARKS

SUBDIVISION NAME	SITE ADDRESS	ACRES	NO. OF SPACES	UNITS PER ACRE	CITY OF...




Exhibit C2.8:
Hansen
Dairy, Feedlot, and Gravel Pit Map
HWY 20/26
1ST LN E
LOCKER AVE
HWY 95
ISLAND RD
ROCKY RD
UPRR
GRANDVIEW RD
GRANDVIEW AVE
Subject Property
FISK RD
FORT LN
NICHOL LN
ADA LN
WARD LN
LEIGH LN
MANN LN
PEARL RD
DOT LN
APPLE VALLEY RD
PARMA RD
LOUISE LN
UPRR
PITMAN LN
HURTZ RD
VALERIE LN
OLD FORT BOISE RD
SHELTON RD
PENCE LN
UPRR
KLAHR RD
FEEDLOTS
DAIRIES
GRAVELPITS
0
1
2
Miles

Exhibit C2.9:

Hansen
Lot Classification Map





Lot Size

- 0.0 - 1.0
- 1.1 - 2.0
- 2.1 - 3.0
- 3.1 - 4.0
- 4.1 - 5.0
- 5.1 - 6.0

- INTERSTATE
- OTHER FREEWAY/ EXPRESSWAY
- PROPOSED OTHER FREEWAY/ EXPRESSWAY
- PRINCIPAL ARTERIAL
- PROPOSED PRINCIPAL ARTERIAL
- MINOR ARTERIAL
- PROPOSED MINOR ARTERIAL
- COLLECTOR
- PROPOSED COLLECTOR

0 0.25 0.5 Miles


SOIL INFORMATION IS DERIVED FROM THE USDA'S CANYON COUNTY
Exhibit C2.10:
Hansen
Soil Map
Grandview
Hwy 95
Ward
4
6
3
Nitrate Priority Wells
0.005000 - 2.000000
2.000001 - 5.000000
5.000001 - 10.000000
10.000001 - 49.800000
IDWR_2C_Geothermal_
Wetlands
0
0.25
Miles


SOIL INFORMATION IS DERIVED FROM THE USDA'S CANYON COUNTY SOIL SURVEY OF 2018
Hansen
Prime Farm Lands
ROCKY
ISLAND RD
GRANDVIEW RD
GRANDVIEW AVE
Subject Property
WARD LN
HWY 95
TAXLOTS
City_Limits
WETLANDS
2C_Hydro
FARMLAND
Farmland of statewide importance
Farmland of statewide importance, if irrigated
Farmland of statewide importance, if irrigated and reclaimed of excess salts and sodium
Not prime farmland
Water/Gravel Pit/ Rock outcrop/ Riverwash/ Terrace Escarpments
Prime farmland if irrigated
Prime farmland if irrigated and drained
Prime farmland if irrigated and reclaimed of excess salts and sodium
0
0.125
0.25
Miles

SOIL REPORT


SOIL CAPABILITY CLASS	SOIL CAPABILITY	SQUARE FOOTAGE	ACREAGE	PERCENTAGE
3	MODERATELY SUITED SOIL	11753.87	0.27	2.39%
6	LEAST SUITED SOIL	237849.17	5.46	48.33%
4	MODERATELY SUITED SOIL	242482.63	5.57	49.28%
		492085.67	11.30	100%

FARMLAND REPORT

SOIL NAME	FARMLAND TYPE	SQUARE FOOTAGE	ACREAGE	PERCENTAGE
GwB	Prime farmland if irrigated	11753.87	0.27	2.39%
NsD2	Not prime farmland	237849.17	5.46	48.33%
NsC	Farmland of statewide importance, if irrigated	242482.63	5.57	49.28%
		492085.67	11.30	100%

SOIL INFORMATION IS DERIVED FROM THE USDA's CANYON COUNTY SOIL SURVEY OF 2018


GRADE	SOILTYPE
1	BEST SUITED SOIL
2	BEST SUITED SOIL
3	MODERATELY SUITED SOIL
4	MODERATELY SUITED SOIL
5	LEAST SUITED SOIL
6	LEAST SUITED SOIL
7	LEAST SUITED SOIL
8	LEAST SUITED SOIL
9	LEAST SUITED SOIL


Exhibit C2.11:
IMAGES WERE FLOWN IN THE 2022/2023.
Grandview Rd
Grandview Ave
Hansen
Contour Map
2285
2280
2290
2295
2300
2305
2320
2330
2315
2310
2335
2325
2345
2340
2365
2350
2355
2360
2330
2340
2335
2345
Hwy 95
Ward Ln
APPLE VALLEY LAND CO
Legend
SUBJECT_PROPERTY
TaxParcels
SectionContours
Wetlands
0 200 400 600
Feet

NITRATE PRIORITY AND WELL INFORMATION IS DERIVED FROM T
NITRATE PRIORITY 2020.

Exhibit C2.12:

Hansen
Nitrate Priority & Wells



GEO-THERMAL LOCATIONS


WETLANDS


NITRATE_PRIORITY

DEQ WELLS
N03_MGL

- 0.005 - 2.00
- 2.000001 - 5.00
- 5.0000001 - 10.00
- 10.000001 - 49.80

0 0.5 1 Miles


Exhibit C2.13:
Hansen
TAZ Household
1ST LN
LOCKER AVE
TAZ NO. 2024
HOUSEHOLD. 15
RIVER BLUFF RD
HWY 95
ISLAND RD
ROCKY RD
TAZ NO. 2062
HOUSEHOLD. 27
GRANDVIEW RD
GRANDVIEW AVE
Subject Property
FISK RD
TAZ NO. 2066
HOUSEHOLD. 0
WARD LN
NICHOL LN
ADA LN
APPLE VALLEY RD
NOB LN
PEARL RD
DOT LN
STUBB LN
PARMA RD
TAZ NO. 2064
HOUSEHOLD. 1
HURTZ RD
TAZ NO. 2065
HOUSEHOLD. 2
TAZ NO. 2061
HOUSEHOLD. 1
TAZ NO. 2060
HOUSEHOLD. 0
TAZ NO. 2063
HOUSEHOLD. 1
TAZ NO. 2025
HOUSEHOLD. 0
TAZ NO. 2026
HOUSEHOLD. 1
N
W
E
S
CANYON COUNTY, IDAHO
DEVELOPMENT SERVICES
GEOGRAPHICAL INFORMATION SYSTEMS
House Hold 2025-2050
-4 - 50
51 - 150
151 - 250
251 - 500
501 - 750
751 - 1263
0
0.5
1
Miles


Hansen
TAZ Jobs
LOCKER AVE
1ST LN E
TAZ NO. 2024
JOBS. -2
RIVER BLUFF RD
HWY 95
ISLAND RD
ROCKY RD
TAZ NO. 2062
JOBS. -3
GRANDVIEW RD
GRANDVIEW AVE
Subject Property
FISK RD
TAZ NO. 2066
JOBS. 0
WARD LN
NICHOL LN
ADA LN
APPLE VALLEY RD
PEARL RD
DOT LN
NOB LN
STUBB LN
TAZ NO. 2064
JOBS. -3
HURTZ RD
TAZ NO. 2065
JOBS. 0
TAZ NO. 2061
JOBS. 0
PARMA RD
TAZ NO. 2060
JOBS. -1
TAZ NO. 2063
JOBS. 0
TAZ NO. 2025
JOBS. 0
TAZ NO. 2026
JOBS. -1
N
W
E
S
CANYON COUNTY, IDAHO
DEVELOPMENT SERVICES
GEOGRAPHICAL INFORMATION SYSTEMS
Jobs 2025-2050
-1
0 - 100
101 - 250
251 - 500
501 - 1000
1001 - 2148
0
0.5
1
Miles




Exhibit C2.14:
Hansen
Slope Percent Map
IDAHO INVE
Grandview Ave
Hwy 95
Ward Ln
APPLE VALLEY LAND CO
Slope Percent
0.001 - 3
3.001 - 6
6.001 - 9
9.001 - 12
12.001 - 14.999
15 - 202.718
0
200
400
600
Feet

Exhibit C2.15:

Hansen
Future Land Use Map



CANYON COUNTY, IDAHO
DEVELOPMENT SERVICES
GEOGRAPHICAL INFORMATION SYSTEMS

N W E S

Overlay Districts 2030

- AGRI-TOURISM BUSINESS USE
- AGRI-TOURISM EXCLUSIVE FARM USE
- INTENSIVE AGRICULTURE OVERLAY
- CALDWELL AIRPORT OVERLAY
- NAMPA AIRPORT OVERLAY
- HISTORIC PRESERVATION
- HOUSING AUTHORITY

Future Land Use 2030

- COMMERCIAL
- INDUSTRIAL
- RESIDENTIAL
- RURAL RESIDENTIAL

0 0.5 1 Miles



Exhibit C2.16:
Hansen
Notification Map
Un
Island Rd
Rocky Rd
Grandview Rd
Grandview Ave
28094
28263
28251
32925
32501
28282
Ward Ln
Hwy 95
Pearl Rd
Slate Ln
Dot Ln
Winecup Ln
DISTANCE PARCELS
1000 Feet 9
0 0.25 0.5
Miles
CANYON COUNTY, IDAHO
DEVELOPMENT SERVICES
GEOGRAPHICAL INFORMATION SYSTEMS
N
W
E
S

Exhibit C2.17:






Exhibit C3:


WASHINGTON COUNTY
OREGON
GEM COUNTY
CANYON COUNTY
ADA COUNTY
Payette
Fruitland
New Plymouth
Snake River
Payette River
OX RANCH RD
LITTLE WILLOW RD
DRY CREEK RD
STONE QUARRY RD
BIG WILLOW RD
SUCKER CREEK RD
BIG FLAT RD
FOUR MILE RD
HELL RD
RIVER RD
NE 19TH AVE
SOUTH PAYNE RD
PAYETTE HEIGHTS RD
HORN AVE
9TH AVE N
CENTER AVE
6TH AVE S
CLAY PEAK RD
KILLEBREW DR
WASHOE RD
NW 4TH AVE
BUTTE RD
DENVER RD
NW 2ND AVE
S WHITLEY DR
CUSTER RD
NW 1ST AVE
ADAMS RD
HOLLY AVE
SW 1ST AVE
SW 2ND AVE
SW 3RD AVE
SW 4TH AVE
SPEAS RD
GLENWAY AVE
FAIRVIEW AVE
ECHO AVE
SE 1ST AVE
SE 2ND AVE
SE 3RD AVE
SE 4TH AVE
BLAINE RD
CASSIA RD
ELGIN RD
FREEMONT RD
1ST LN E
ELMORE RD
PEARL RD
OLD HWY 30
SAND HOLLOW RD
GRESS RD
SE 9TH AVE
SE 11TH AVE
OASIS RD
BLUFF RD
GULCH RD
Proposed Future Land Uses
Agriculture Preservation
Agriculture Rangeland
Agriculture Mixed
Residential Rural
Commercial
Industrial
Recreation Sites/Areas
Payette County Boundary
City Limits
Area of City Impact
Parcels
PAYETTE COUNTY
IDAHO
PAYETTE
FRUITLAND
NEW PLYMOUTH
N

ArcGIS Web Map

Exhibit C4:



4/6/2026, 4:42:06 PM

1:52,159

0 0.47 0.95 1.9 mi

0 0.75 1.5 3 km

Payette County Mask

Parcels

Zoning

COMMERCIAL 1

COMMERCIAL 2

INDUSTRIAL 1 - LIGHT

INDUSTRIAL 2 - HEAVY

RECREATIONAL

RESIDENTIAL

World_Hillshade

Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community, Esri, NASA, NGA, USGS, FEMA

Exhibit D:

EXHIBIT D


Site Visit Photos: March 25, 2026

Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 21, 2026

Site Photos: Taken March 25, 2026



Photos 1-8 taken on Highway 95 from the parcels' approach.



Photo 1: Taken on Highway 95 from the parcels approach, facing north from the subject property.



Photo 2: Taken on Highway 95 from the parcels approach, facing northeast from the subject property.



Photo 3: Taken on Highway 95 from the parcels approach, facing east from the subject property.



Photo 4: Taken on Highway 95 from the parcels approach, facing southeast from the subject property.



Photo 5: Taken on Highway 95 from the parcels approach, facing south from the subject property.




Photo 6: Taken on Highway 95 from the parcels approach, facing southwest from the subject property.



Photo 7: Taken on Highway 95 from the parcels approach facing west towards the subject property and the proposed use.



Photo 8: Taken on the parcels approach facing west towards the subject property and the proposed use.



Photos 9-11 taken on the subject property.



Photo 9: Taken on the subject property facing north towards the proposed use.



Photo 10: Taken on the subject property facing west towards the proposed use.



Photo 10: Taken on the subject property facing south. In this photo, you can see the property owner's primary residence.



Photo 11: Taken on the subject property facing east towards Highway 95.

Exhibit E:

EXHIBIT E

Agency Comments Received by: May 11, 2026

Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 21, 2026

Exhibit E1:

1445 N Orchard St
Boise, ID 83706 • (208) 373-0550

Brad Little, Governor
Jess Byrne, Director

December 1, 2025

Amber Lewter, Planner
111 North 11th Ave.
Ste. 310
Caldwell, Idaho, 83605
amber.lewter@canyoncounty.id.gov

Subject: Agency Notice CU2025-0031 / Hansen

Dear Ms. Lewter:

Thank you for the opportunity to respond to your request for comment. While DEQ does not review every project on a project-specific basis, we attempt to provide the best review of the information provided. DEQ encourages agencies to review and utilize the Idaho Environmental Guide to assist in addressing project-specific conditions that may apply. This guide can be found at: https://www2.deq.idaho.gov/admin/LEIA/api/document/download/15083.

The following information does not cover every aspect of this project; however, we have the following general comments to use as appropriate:

1. AIR QUALITY

- Please review IDAPA 58.01.01 for all rules on Air Quality, especially those regarding fugitive dust (58.01.01.651), trade waste burning (58.01.01.600-617), and odor control plans (58.01.01.776).

  For questions, contact David Luft, Air Quality Manager, at (208) 373-0550.

- IDAPA 58.01.01.201 requires an owner or operator of a facility to obtain an air quality permit to construct prior to the commencement of construction or modification of any facility that will be a source of air pollution in quantities above established levels. DEQ asks that cities and counties require a proposed facility to contact DEQ for an applicability determination on their proposal to ensure they remain in compliance with the rules.

  For questions, contact the DEQ Air Quality Permitting Hotline at 1-877-573-7648.

2. WASTEWATER AND RECYCLED WATER

- DEQ recommends verifying that there is adequate sewer to serve this project prior to approval. Please contact the sewer provider for a capacity statement, declining balance report, and willingness to serve this project.
- IDAPA 58.01.16 and IDAPA 58.01.17 are the sections of Idaho rules regarding wastewater and recycled water. Please review these rules to determine whether this or future projects will require DEQ approval. IDAPA 58.01.03 is the section of Idaho rules regarding subsurface disposal of wastewater. Please review this rule to determine whether this or future projects will require permitting by the local public health district.
- All projects for construction or modification of wastewater systems require preconstruction approval. Recycled water projects and subsurface disposal projects require separate permits as well.
- DEQ recommends that projects be served by existing approved wastewater collection systems or a centralized community wastewater system whenever possible. Please contact DEQ to discuss potential for development of a community treatment system along with best management practices for communities to protect groundwater.
- DEQ recommends that cities and counties develop and use a comprehensive land use management plan, which includes the impacts of present and future wastewater management in this area. Please schedule a meeting with DEQ for further discussion and recommendations for plan development and implementation.

  For questions, contact Valerie Greear, Water Quality Engineering Manager at (208) 373-0550.

3. DRINKING WATER

- DEQ recommends verifying that there is adequate water to serve this project prior to approval. Please contact the water provider for a capacity statement, declining balance report, and willingness to serve this project.
- DEQ recommends verifying if the current and/or proposed drinking water system is a regulated public drinking water system. A drinking water system is a Public Water System (PWS) if it has at least 15 service connections or regularly serves an average of 25 or more people per day for at least 60 days per year (refer to the DEQ website at: https://www.deq.idaho.gov/water-quality/drinking-water/). For non-regulated systems, DEQ recommends annual testing for total coliform bacteria, nitrate, and nitrite.
- IDAPA 58.01.08 is the section of Idaho rules regarding public drinking water systems. Please review these rules to determine whether this or future projects will require DEQ approval.
- All projects for construction or modification of public drinking water systems require preconstruction approval.
- If any private wells will be included in this project, we recommend that they be tested for total coliform bacteria, nitrate, and nitrite prior to use and retested annually thereafter.
- DEQ recommends using an existing drinking water system whenever possible or construction of a new community drinking water system. Please contact DEQ to discuss this project and to explore options to both best serve the future residents of this development and provide for protection of groundwater resources.
- DEQ recommends cities and counties develop and use a comprehensive land use management plan which addresses the present and future needs of this area for adequate, safe, and sustainable drinking water. Please schedule a meeting with DEQ for further discussion and recommendations for plan development and implementation.

For questions, contact Valerie Greear, Water Quality Engineering Manager at (208) 373-0550.

4. SURFACE WATER

- A Construction General Permit from DEQ may be required for projects that meet the eligibility criteria and have an allowable discharge of storm water or authorized non-storm water associated with construction activities. For questions, contact Emily Montague, IPDES Compliance Supervisor, at (208) 813-0872.

- Please contact DEQ to determine whether this project will require an Idaho Pollutant Discharge Elimination System (IPDES) Permit. A Multi-Sector General Permit from DEQ may be required for facilities that have an allowable discharge of storm water or authorized non-storm water associated with the primary industrial activity and co-located industrial activity. For questions, contact Emily Montague, IPDES Compliance Supervisor, at (208) 373-0433.

- If this project is near a source of surface water, DEQ requests that projects incorporate construction best management practices (BMPs) to assist in the protection of Idaho's water resources. Additionally, please contact DEQ to identify BMP alternatives and to determine whether this project is in an area with Total Maximum Daily Load stormwater permit conditions.

- The Idaho Stream Channel Protection Act requires a permit for most stream channel alterations. Please contact the Idaho Department of Water Resources (IDWR), Western Regional Office, at 2735 Airport Way, Boise, or call (208) 334-2190 for more information. Information is also available on the IDWR website at: https://idwr.idaho.gov/streams/stream-channel-alteration-permits.html

- The Federal Clean Water Act requires a permit for filling or dredging in waters of the United States. Please contact the US Army Corps of Engineers, Boise Field Office, at 10095 Emerald Street, Boise, or call 208-345-2155 for more information regarding permits.

  For questions, contact Lance Holloway, Surface Water Manager, at (208) 373-0550.

5. SOLID WASTE, HAZARDOUS WASTE AND GROUNDWATER CONTAMINATION

- **Solid Waste.** No trash or other solid waste shall be buried, burned, or otherwise disposed of at the project site. These disposal methods are regulated by various state regulations including Idaho's Solid Waste Management Regulations and Standards (IDAPA 58.01.06), Rules and Regulations for Hazardous Waste (IDAPA 58.01.05), and Rules and Regulations for the Prevention of Air Pollution (IDAPA 58.01.01). Inert and other approved materials are also defined in the Solid Waste Management Regulations and Standards.

- **Hazardous Waste.** The types and number of requirements that must be complied with under the federal Resource Conservations and Recovery Act (RCRA) and the Idaho Rules and Standards for Hazardous Waste (IDAPA 58.01.05) are based on the quantity and type of waste generated. Every business in Idaho is required to track the volume of waste generated, determine whether each type of waste is hazardous, and ensure that all wastes are properly disposed of according to federal, state, and local requirements.

- **Water Quality Standards.** Site activities must comply with the Idaho Water Quality Standards (IDAPA 58.01.02) regarding hazardous and deleterious-materials storage, disposal, or accumulation adjacent to or in the immediate vicinity of state waters (IDAPA 58.01.02.800); and the cleanup and reporting of oil-filled electrical equipment (IDAPA 58.01.02.849); hazardous materials (IDAPA 58.01.02.850); and used-oil and petroleum releases (IDAPA 58.01.24.060 and 58.01.24.061). Petroleum releases must be reported to DEQ in accordance with IDAPA 58.01.24.060.01 and 58.01.24.061.04. Hazardous material releases to state waters, or to land such that there is likelihood that it will enter state waters, must be reported to DEQ in accordance with IDAPA 58.01.02.850.
- **Groundwater Contamination.** DEQ requests that this project comply with Idaho's Ground Water Quality Rules (IDAPA 58.01.11), which states that "No person shall cause or allow the release, spilling, leaking, emission, discharge, escape, leaching, or disposal of a contaminant into the environment in a manner that causes a ground water quality standard to be exceeded, injures a beneficial use of ground water, or is not in accordance with a permit, consent order or applicable best management practice, best available method or best practical method."

  For questions, contact Matthew Pabich, Waste & Remediation Manager, at (208) 373-0550.

6. ADDITIONAL NOTES

- If an underground storage tank (UST) or an aboveground storage tank (AST) is identified at the site, additional regulations may apply. If an UST is present, the site should be evaluated to determine whether the UST is regulated by DEQ. If an AST is identified, EPA may have additional requirements. Both UST and AST sites should be assessed to determine whether there is potential soil and ground water contamination. Please call DEQ at (208) 373-0550, or visit the DEQ website https://www.deq.idaho.gov/waste-management-and-remediation/storage-tanks/leaking-underground-storage-tanks-in-idaho/ for assistance. If applicable to this project, DEQ recommends that BMPs be implemented for any of the following land uses: wash water from cleaning vehicles, fertilizers and pesticides, animal facilities, composted waste, ponds and outdoor gun ranges. Please contact DEQ for more information on any of these conditions.

We look forward to working with you in a proactive manner to address potential environmental impacts that may be within our regulatory authority. If you have any questions, please contact me, or any of our technical staff at (208) 373-0550.

Sincerely,



Troy Smith
Regional Administrator

Exhibit E2:

Your Safety • Your Mobility
Your Economic Opportunity

IDAHO TRANSPORTATION DEPARTMENT
P.O. Box 8028 • Boise, ID 83707-2028
(208) 334-8300 • itd.idaho.gov

December 4, 2025

Amber Lewter
Planner
111 North 11th Ave, Suite 310
Caldwell, ID 83605

VIA EMAIL

Development Application	CU2025-0031
Project Name	Hansen Slaughterhouse
Project Location	Parcel R39357012
Project Description	Slaughterhouse
Applicant	Lucas Hansen

The Idaho Transportation Department (ITD) reviewed the referenced application(s) and has the following comments:

1. ITD does not have any concerns with the proposed project, so long as the following requirements are met:
    a. Any access onto a state highway will need to be permitted through our online system, which can be found here.
    b. A commercial two-way approach will need to meet current specs, which include:
        i. Width between 25'-40'
        ii. Radii between 30'- 40'
        iii. Paving the approach and any part of the driveway that is within ITD's right-of-way
            1. ITD's ROW here is 100' from centerline
        iv. Per IDAPA 39.03.42.05, please align your new approach with one of the existing residential approaches across the highway. At a minimum, the new approach needs to be 650' north of the US-95/Ward Lane intersection.
2. ITD reserves the right to make further comments upon review of the submitted documents.

If you have any questions, you may contact me at 208-334-8377.

Sincerely,

Kendra Conder

Kendra Conder
Development Services Coordinator
Kendra.conder@itd.idaho.gov

Exhibit E2.1:

Archived: Tuesday, April 28, 2026 3:08:38 PM
From: Kendra Conder
Mail received time: Tue, 7 Apr 2026 17:37:27
Sent: Tue, 7 Apr 2026 17:37:11
To: Amber Lewter
Subject: RE: [External] Agency Notice CU2025-0031 / Hansen
Importance: Normal
Sensitivity: None

Hi Amber,

The application indicates it's a relatively a small operation so I don't expect any traffic concerns. I've talked with Dan about trying to be more thorough in my responses, so moving forward you should see more in-depth responses from me! But for this one I'll do my best to explain the reasoning.

When applications don't provide traffic estimates, I reference our engineering manual to review trip generation. Our transportation/engineering manual doesn't have traffic data for a butcher shop, so the closest I can get for traffic estimates is a small office building in an urban area.

AM peak hour estimates (7am-9am) is 16 vehicles.
PM peak hour estimates (4-6pm) is 13 vehicles.

Based on traffic information for the most comparable business type, I don't foresee a rural butcher shop generating enough traffic to be a concern. The county is always welcome to require additional traffic analysis even if ITD does not!

Kendra Conder
District 3 | Development Services Coordinator
Idaho Transportation Department
Office: 208-334-8377
Cell: 208-972-3190



From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Monday, April 6, 2026 11:40 AM
To: Kendra Conder <Kendra.Conder@itd.idaho.gov>
Subject: RE: [External] Agency Notice CU2025-0031 / Hansen

CAUTION: This email originated outside the State of Idaho network. Verify links and attachments BEFORE you click or open, even if you recognize and/or trust the sender. Contact your agency service desk with any concerns.

Hello Kendra,

Is there any concern for the impact on traffic for this case?

Thank you,

Exhibit E2.2:

Archived: Tuesday, April 28, 2026 3:08:45 PM
From: Kendra Conder
Mail received time: Tue, 28 Apr 2026 18:30:13
Sent: Tue, 28 Apr 2026 18:29:55
To: Amber Lewter
Subject: [External] RE: CU2025-0031
Importance: Normal
Sensitivity: None

To my knowledge it will need to be a new access/permit. It looks like there's an old farm field approach, but it won't meet any of our standards.

Kendra Conder
District 3 | Development Services Coordinator
Idaho Transportation Department
Office: 208-334-8377
Cell: 208-972-3190



From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Tuesday, April 28, 2026 10:33 AM
To: Kendra Conder <Kendra.Conder@itd.idaho.gov>
Subject: CU2025-0031

CAUTION: This email originated outside the State of Idaho network. Verify links and attachments BEFORE you click or open, even if you recognize and/or trust the sender. Contact your agency service desk with any concerns.

Hello Kendra,

Can you tell me if the access for the slaughterhouse is an existing access off of Hwy 95 or will the applicant need to request a new access?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov
Website: www.canyoncounty.id.gov

Development Services Department (DSD)

Exhibit E3:

Archived: Tuesday, April 28, 2026 3:08:55 PM
From: Stevie Harris
Mail received time: Tue, 7 Apr 2026 14:52:28
Sent: Tue, 7 Apr 2026 14:52:11
To: Amber Lewter
Subject: [External] RE: CU2025-0031
Importance: Normal
Sensitivity: None

Morning Amber,

ISDA has no jurisdiction over slaughter facilities. They would need to coordinate with DEQ on the management of their waste products. It's best to reach out to DEQ.

Hope that helps.

Stevie Harris
Deputy Director - Operations
Idaho State Department of Agriculture
Ph: (208) 332-8552
F: (208) 334-2170

From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Monday, April 6, 2026 2:08 PM
To: Stevie Harris <Stevie.Harris@ISDA.IDAHO.GOV>
Subject: CU2025-0031

CAUTION: This email originated outside the State of Idaho network. Verify links and attachments BEFORE you click or open, even if you recognize and/or trust the sender. Contact your agency service desk with any concerns.

Hello Stevie,

I have an application for a slaughterhouse. Could you please take a look at the application and share your comments? Is there anything that they would need to do prior to a hearing? Or just before beginning operations?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Exhibit E4:

Archived: Tuesday, April 28, 2026 3:09:03 PM
From: Olson, Aaron
Mail received time: Tue, 7 Apr 2026 20:25:03
Sent: Tue, 7 Apr 2026 20:24:44
To: Amber Lewter
Subject: [External] Re: Water Rights
Importance: Normal
Sensitivity: None

Hi Amber,

After taking a look at the application, they would be able to supply the business using their existing domestic well without needing a new water right as long as their water use does not exceed 2,500 gallons per day. 2,500 gallons per day is the maximum amount allowed under Idaho Code 42-111(b) that allows domestic uses to be exempt from needing a water right. If they will exceed that amount, then they would want to apply for a commercial water right. The area is open for new water rights and a preliminary check shows there are no areas of concern there.

Thanks,

Aaron

From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Tuesday, April 7, 2026 12:29 PM
To: Olson, Aaron <Aaron.Olson@idwr.idaho.gov>
Subject: Water Rights

CAUTION: This email originated outside the State of Idaho network. Verify links and attachments BEFORE you click or open, even if you recognize and/or trust the sender. Contact your agency service desk with any concerns.

Hello,

Could you please review this application and see if the applicant has adequate water rights or if there is anything they will need to do? Are they able to get adequate water rights?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov
Website: www.canyoncounty.id.gov

Development Services Department (DSD)

Exhibit E5:

Archived: Tuesday, April 28, 2026 3:09:11 PM
From: Farmers Cooperative Ditch Company Parma
Mail received time: Wed, 8 Apr 2026 17:48:46
Sent: Wed, 8 Apr 2026 11:48:23
To: Amber Lewter
Subject: [External] Re: CU2025-0031
Importance: Normal
Sensitivity: None
Attachments:
image001.png

I spoke with our Treasurer Tom Johnston,
Although our Canal runs over 200' away, this should not impact our water quality or surface runoff. As long as they are having to abide by all County regulations we have no issue with this CUP. We would be relying on the County implementing all runoff regulations as they are at a higher elevation. We would simply request that there are safeguards in place for animal waste not to run into our canal.
As they are not our shareholders, only in our impact area we do not need to sign anything.
Thank you,
Karan Eby Secretary Farmers' Cooperative Ditch Company

Karan Eby/Courtney Nelson
Secretary/Bookkeeper
Farmers Co-Operative Ditch Company
Phone: (208)722-2010

On Wed, Apr 8, 2026 at 11:35 'a0AM Farmers Cooperative Ditch Company Parma <fcdc1875@gmail.com> wrote:

> I will talk to the board members at our monthly meeting on the 18th.
>
> Thank you,
> Karan
>
> Karan Eby/Courtney Nelson
> Secretary/Bookkeeper
> Farmers Co-Operative Ditch Company
> Phone: (208)722-2010
>
> On Mon, Apr 6, 2026 at 2:11 'a0PM Amber Lewter <Amber.Lewter@canyoncounty.id.gov> wrote:
>
> > Hello,

Could you please review the application and provide comments.

Thank you,

Amber Lewter

Associate Planner

Canyon County Development Services Department

111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631

Email: amber.lewter@canyoncounty.id.gov

Website: www.canyoncounty.id.gov

Development Services Department (DSD)

Public office hours

Monday, Tuesday, Thursday and Friday

8am – 5pm

Wednesday

1pm – 5pm

**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

Exhibit E6:

Archived: Tuesday, April 28, 2026 3:09:25 PM
From: Madelyn Vander Veen
Sent: Thursday, April 16, 2026 2:04:59 PM
To: Amber Lewter
Subject: Agency Notice CU2025-0031 / Hansen
Importance: Normal
Sensitivity: None

Hello Amber,

Regarding case CU2025-0031 / Hansen, if the use is approved, the applicant may receive an address for the slaughterhouse by submitting a building permit. An approach permit will be required. It looks like 3-8 employees will be on site for the use and customers will also be coming to and from. An address is recommended for uses that involve employees and/or customers on site so that emergency services can quickly and accurately locate the site in an emergency situation.

Thanks,

Madelyn Vander Veen
GIS Analyst, Canyon County Development Services
madelyn.vanderveen@canyoncounty.id.gov | Direct: 208-455-6035

DSD public office hours:
Monday, Tuesday, Thursday and Friday: 8am – 5pm
Wednesday: 1pm – 5pm
PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

Exhibit E7:

Archived: Tuesday, April 28, 2026 3:09:34 PM
From: Lucy Ostyn
Sent: Tue, 21 Apr 2026 18:13:34
To: Amber Lewter
Cc: Tom Crosby
Subject: FW: Agency Notice CU2025-0031 / Hansen
Importance: Normal
Sensitivity: None
Attachments:
30 day AGENCY notice PZ hearing.pdf

Amber,

Hopefully it isn't too late for this comment! The AG building on site (ZCA2024-0040) expired and received no inspections.

If they plan on using this structure for the slaughterhouse: a commercial change of occupancy will be required for the structure.
If they plan on building new: the AG building should be rectified and a new commercial building permit should be pulled for the new structure.

Thank you,

Lucy Ostyn
Permitting Supervisor
lucy.ostyn@canyoncounty.id.gov
(208)455-5961
Canyon County Development Services Department
111 N. 11th Ave. #310 Caldwell, ID 83605

DSD PUBLIC OFFICE HOURS
Monday, Tuesday, Thursday and Friday
8am – 5pm
Wednesday
1pm – 5pm

From: Caitlin Ross <Caitlin.Ross@canyoncounty.id.gov>
Sent: Thursday, April 16, 2026 10:28 AM
To: 'tkelly@parmaschools.org' <tkelly@parmaschools.org>; 'Jeff@parmafire.us' <Jeff@parmafire.us>; 'ParmaRuralFire@gmail.com' <ParmaRuralFire@gmail.com>; 'knute.sandahl@doi.idaho.gov' <knute.sandahl@doi.idaho.gov>; gwatkins@nphd.net; brandy.walker@ForgedFiber37.com; 'eingram@idahopower.com' <eingram@idahopower.com>; 'easements@idahopower.com' <easements@idahopower.com>; 'arobins@idahopower.com' <arobins@idahopower.com>; 'monica.taylor@intgas.com' <monica.taylor@intgas.com>; 'jessica.mansell@intgas.com' <jessica.mansell@intgas.com>; 'Contract.Administration.Bid.Box@ziply.com' <Contract.Administration.Bid.Box@ziply.com>; 'developmentreview@blackcanyonirrigation.com' <developmentreview@blackcanyonirrigation.com>; 'fcdc1875@gmail.com'

Exhibit E8:

Archived: Tuesday, April 28, 2026 3:09:43 PM
From: Anthony Lee
Mail received time: Wed, 22 Apr 2026 20:41:23
Sent: Wed, 22 Apr 2026 20:41:05
To: Amber Lewter
Cc: Mitch Kiester
Subject: RE: [External] RE: Agency Notice CU2025-0031 / Hansen
Importance: Normal
Sensitivity: None
Attachments:
Pre.Development.Notes.Signed.04.22.2026.pdf

Hi Amber,

1. Will a Nutrient Pathogen Study be required? **A Nutrient Pathogen Study will not be required.**
2. Will adequate sanitary systems be provided to accommodate the use? **A subsurface sewage disposal permit has been issued and is consistent with the total wastewater design flow specified in the approved Letter of Intended Use.**
3. Any concerns about the use or request for rezoning? If so, are there any conditions or mitigation measures recommended to ensure the use or requested rezone minimizes potential impacts to the surrounding area and nearby city? **There are no concerns with the use or request for rezoning if the applicant meets all SWDH requirements in accordance with IDAPA 58.01.03.**

Please see the attached pre-development notes from 04/22/2026.

Let me know if you have any questions.

Thank you,

SOUTHWEST DISTRICT HEALTH
Check out our new online self-service portal here! PORTAL
Anthony Lee, RS/BS | Land Development Senior
o 208.455.5384 | c 208.899.1285 | f 208.455.5300
anthony.lee@swdh.id.gov | SWDH.org
13307 Miami Ln., Caldwell, ID 83607

From: Anthony Lee
Sent: Wednesday, April 8, 2026 3:44 PM
To: 'Amber Lewter' <Amber.Lewter@canyoncounty.id.gov>
Cc: Mitch Kiester <Mitch.Kiester@swdh.id.gov>
Subject: RE: [External] RE: Agency Notice CU2025-0031 / Hansen

Hi Amber,

Actually, I am still waiting on the applicant to schedule a pre-development meeting. That is not my signature on

that agency acknowledgement form that was dated on 10/01/2025.

Thank you,

Check out our new online self-service portal here! PORTAL
Anthony Lee, RS/BS | Land Development Senior
o 208.455.5384 | c 208.899.1285 | f 208.455.5300
anthony.lee@swdh.id.gov | SWDH.org
13307 Miami Ln., Caldwell, ID 83607

From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Wednesday, April 8, 2026 11:51 AM
To: Anthony Lee <Anthony.Lee@swdh.id.gov>
Cc: Mitch Kiester <Mitch.Kiester@swdh.id.gov>
Subject: RE: [External] RE: Agency Notice CU2025-0031 / Hansen

CAUTION: This email originated outside Southwest District Health's network. Verify links and attachments BEFORE you click or open, even if you recognize and/or trust the sender. Contact IT with any concerns.

Hi Anthony,

Could I get the pre-development notes? Also, are there provisions through SWDH that the applicant will have to take to sell retail of the meat?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov
Website: www.canyoncounty.id.gov

Development Services Department (DSD)
Public office hours
Monday, Tuesday, Thursday and Friday
8am – 5pm
Wednesday
1pm – 5pm
**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a

Exhibit E8.1:

SOUTHWEST DISTRICT HEALTH
Environmental & Community Health Services
EnvironmentalSupport@swdh.id.gov • (208) 455-5400

Pre-Development Meeting

Name of Development: Slaughter House

Applicant: Lucus Hansen

P.E./P.G.: _____

Others In Attendance: _____

of Lots: 1 Wastewater Flow: 639 Gallons Acreage Proposed: 11.30

Location of Development: TBD Hwy 95, Parma, ID 83660

Parcel # : R39357012

Project in Area of Concern: Not located in a NP area Groundwater/Rock <10': >10' GW

Level 1 NP Study Required: ☐ Yes ☑ No ☐ Pending

LSAS/CSS Proposed: N/A

Proposed Drinking Water: ☑ Individual ☐ City ☐ Community ☐ Public Water Supply ☐ Pending

Information Distributed: ☐ SER ☐ NP Guidance ☑ Non-Domestic WW AP ☐ Pending

Description of Projects:

The applicant met with Southwest District Health (SWDH) to discuss the proposed development of a slaughterhouse facility consisting of processing up to 36 animals with five (5) employees on an 11.30-acre parcel.

The parcel is not located within a designated Nitrate Priority Area; therefore, a Nutrient Pathogen (NP) Study is not required.

A Letter of Intended Use has been submitted and approved by SWDH and the Idaho Department of Environmental Quality (IDEQ), and a subsurface sewage disposal permit has been issued for the proposed use.

It was identified that the originally proposed drainfield location encroaches into an area subject to vehicle traffic, which may result in soil compaction and compromise system performance. As a result, new test holes will be required in an alternate location to evaluate site suitability for a revised drainfield area that avoids vehicle traffic impacts.

An irrigation canal is located on the property; the proposed drainfield area must maintain a minimum setback of at least 50 feet from the canal in accordance with IDAPA 58.01.03.

Anthony Lee


Date: 04/22/2026

Exhibit E8.2:

Public Health
Prevent. Promote. Protect.
Idaho Public Health Districts

Please draw an aerial view of the property showin
property lines, well location(s), water lines, location of septic tank and drainfields, location of drainfield replacement area, ditches and streams, easements and right of ways, driveway and parking area, cut banks, and location of street or road. Indicate dimensions and separation distances of each from septic tank and drainfield.

PLOT PLAN SCALE: 1" = ____'



Southwest District Health, 13307 Miami Lane, P. O. Box 850, Caldwell, ID 83606
Phone: 208.455.5400, Fax: 208.455.5405

SIGNATURE: _____ DATE: 9-25-25

By my signature above, I certify that all answers and statements on this application are true and complete to the best of my knowledge. I understand that should evaluation disclose untruthful or misleading answers, my application may be rejected or my permit canceled. I understand that any deviation from the plans, conditions, and specifications, is prohibited unless it is approved in advance by the Director or his designee. I hereby authorize the Health District to have access to this property for the purpose of conducting a site-evaluation.

(Official Use Only)

Plot Plan Approval Date:_____ EHS Name:_____ EHS # :_____

Revision Date: 06/17/2010



02/03/2026
Anthony Lee
North
6'
6'min
6'
71' each trench (min)
Size dependent 1704 Gallons
on service provider
(min)
6'min
3'min
ETPS Tank
Septic Tank
Shop
Hwy 95
100'
18'
Replacement Area
71'

Exhibit E8.3:

Archived: Wednesday, April 29, 2026 3:27:11 PM
From: Anthony Lee
Mail received time: Wed, 29 Apr 2026 20:00:11
Sent: Wed, 29 Apr 2026 19:59:56
To: Amber Lewter
Cc: Mitch Kiester
Subject: RE: [External] RE: Agency Notice CU2025-0031 / Hansen
Importance: Normal
Sensitivity: None

Hi Amber,

A septic permit was issued to account for blood waste and had approval from DEQ.

Let me know if you have any questions.

Thank you,

SOUTHWEST DISTRICT HEALTH

Check out our new online self-service portal here! PORTAL
Anthony Lee, RS/BS | Land Development Senior
o 208.455.5384 | c 208.899.1285 | f 208.455.5300
anthony.lee@swdh.id.gov | SWDH.org
13307 Miami Ln., Caldwell, ID 83607

From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Wednesday, April 29, 2026 1:57 PM
To: Anthony Lee <Anthony.Lee@swdh.id.gov>
Cc: Mitch Kiester <Mitch.Kiester@swdh.id.gov>
Subject: RE: [External] RE: Agency Notice CU2025-0031 / Hansen

CAUTION: This email originated outside Southwest District Health's network. Verify links and attachments BEFORE you click or open, even if you recognize and/or trust the sender. Contact IT with any concerns.

Hi Anthony,

Thank you for sending this over to me. I was checking with the applicant on what he was going to do with the waste that cannot be picked up such as the blood. He said that he had to get a special septic permit for such items. Can you confirm this is correct?

Thank you,

Amber Lewter

Exhibit E9:

Archived: Wednesday, April 29, 2026 3:29:27 PM
From: Ricky Galvan
Mail received time: Wed, 29 Apr 2026 13:20:55
Sent: Wednesday, April 29, 2026 7:20:57 AM
To: Amber Lewter
Subject: [External] Licensing Resources for Meat Processors
Importance: Normal
Sensitivity: None
Attachments:
Meat Processing SOP.pdf; ISDA Information (1).pdf;

Hi Amber,

Attached you will find more resources for the client regarding the processing of meat.

Let me know if you have any questions.

Thanks!

SOUTHWEST DISTRICT HEALTH
Ricky Galvan | Environmental Health Specialist
o 208.795.6023 | c 208.899.1288
ricky.galvan@swdh.id.gov | SWDH.org
13307 Miami Ln., Caldwell, ID 83607

Healthier Together

Exhibit E9.1:

IDAHO FOOD PROTECTION PROGRAM

IDAHO'S LICENSING GUIDANCE TABLE
FOOD PROCESSING AND STORAGE

Type, code, description	License	Notes
615-010 Food Processor: Manufacturer of food for wholesale distribution. Does not provide food directly to consumer. Licensure for processors is required whether food is potentially hazardous or non-potentially hazardous. Risk category should be assigned based on type of food and processing. For example, candy or cookies would be medium risk and refrigerated salsa would be high risk.	**Yes**	Health District will license and inspect for first year of operation, EXCEPT for: • Low-acid canned food • Acidified food (except those requiring refrigeration) • Juices • Seafood • Salvage operations • Any meat processing (which must be USDA inspected) Information related to interstate sales must be collected during annual inspection. After first year of operation, firm may be referred to FDA for jurisdiction. Please see Appendix B for protocol on referring firms to FDA.
615-010: Ice processor. Manufacture of ice for wholesale distribution.	**Yes**	Licensing required. High risk or medium risk, depending on water source
615-020: Beverage Bottling: Manufacture and bottling of beverages for wholesale distribution.	**Yes**	See note above. High or medium risk, depending on beverage.
615-030: Multi-warehouse: A wholesale storage facility where food is stored prior to distribution.	**Yes**	See note above. Medium risk
615-030 Storage locker: A wholesale storage facility with food held refrigerated or frozen	**Yes**	Licensing required if operation is intrastate. Medium risk
615-030 Rabbit or poultry processing: Any number of rabbits and less than 20,000 poultry per year sold **intrastate** only	**Yes**	Licensing required for processing facility, with special conditions on inspection and labeling per written guidelines and Idaho Food Code Section 3-201.11. High risk
Custom Meat Processor	**No**	USDA jurisdiction, except that any retail sales are licensed by the health district (612-073,

		medium risk). Meat sold retail must be from a plant with continuous USDA inspection.
Retail Meat Vendor	**Yes**	USDA inspection does not extend to retail sales of meat.
615-020 Water processing and bottling: A facility that processes and distributes water wholesale	**Yes**	Licensing by health district for first year of operation. High risk or medium risk.

IDAHO FOOD PROTECTION PROGRAM

IDAHO'S LICENSING GUIDANCE TABLE
SCHOOL LUNCH AND ASSOCIATED OPERATIONS

Type, code, description	License	Notes
616-090 Elementary schools, private or public, with preparation of PHF	**Yes**	Highly susceptible population makes this type of facility high risk.
616-091 Middle or high schools, private or public, with preparation of PHF	**Yes**	Usually medium risk.
616-091 Satellite school lunch facilities	**Yes**	Food is prepared at another licensed location and transported hot or cold. Medium risk.
616-091 School warehouse: Storage facility of PHF for a school or a school district	**Yes**	No licensing is required if only non-PHF stored. Medium risk.

VENDING OPERATIONS

605-041 Commissary for food vending operation with PHF	**Yes**	License required for base of operation where food is prepared and stored prior to delivery to vending machines. Medium risk.
605-041 Vending machines with PHF	**Units Of Commissary**	License for commissary includes all machines with PHF's. Machines are not licensed separately, but a representative number of machines are inspected when the commissary is inspected. Medium risk.
605-041 Vending machines that are treating municipal drinking water and customer fills a container to take home.	**Maybe**	If the food establishment where the water vending machine is located does not assume responsibility for the machine under its license, it may be licensed separately. Medium risk.

Exhibit E9.2:

The USDA typically regulates the following business types:

- Slaughterhouses; Meat Processors; Poultry Processors; Egg Processors; Food Processors whose products contain meat (See Examples of Food Product Jurisdiction Table)

Food products with the following characteristics are regulated by the USDA.

- Contains >2% cooked meat
- Contains >3% raw meat
- Contains >30% fat, tallow or meat extract
- Contains >2% cooked poultry
- Contains >10% cooked poultry skins, giblets, fat

Examples of Business Regulation

Business	Description of Operations	Federal Jurisdiction
Meat Product Processor	Producer of frozen meat pies, bone broth, steak delivered via mail	USDA
Poultry Product Processor	Poultry processor	USDA
Egg Product Processor[1]	Produces dried, freeze dried, frozen, liquid, & egg substitutes	USDA
Egg Processing Plant	Egg washing, sorting, packing	FDA
Slaughterhouse[2,3] (For Amenable Species or Voluntary/Fee-For-Service Inspection)	Slaughter and processing of carcasses for sale.	USDA
Commissary for Retail Outlets	A commissary produces deli meats to sell at multiple delis, all owned by the same company. Products are shipped ready-to-eat.	FDA
Restaurants and Retail Establishments	Retail establishment that sells meat to typical consumers in retail quantities	Department of Health (County/State)

[1]Egg products amenable to the Egg Products Inspection Act are prepared from shell eggs of domesticated chickens, turkeys, ducks, geese, and guineas.

[2]Amenable Species

[3]Voluntary/Fee-For-Service Inspection: reindeer, elk, deer, antelope, water buffalo, bison, rabbits, migratory waterfowl, and game bird products.

Examples of Food Product Jurisdiction

Product	Jurisdiction
Burritos (Containing > 2% Cooked Meat or Poultry)	USDA
Casings, Natural	FDA
Cheese and Meat/Poultry Separated in Package and Total Package Has More > 2% Cooked Meat	USDA
Cheese Balls That Contain <50% Meat/Poultry	FDA
Cheese Balls That Contain >50% Meat/Poultry	USDA
Dried Meat/Poultry Soup Mixes	FDA
Fajita Meat/Poultry in a Tortilla	USDA or FDA[5]
Hot Dog - Bagel Dogs	FDA[4]
Hot Dog - Corndogs	USDA
Hot Dog - Pretzel Dogs	USDA
Hot Dog in a Bun	FDA
Hot Pocket Type Sandwiches that Contain >2% Cooked Meat	USDA
Kits – with separate components (to include meat and poultry)	

- Salad Kit - Breakfast Scramble Kit - Slow Cooker (Crock Pot) Kit - Meat Kit * Package disassembly may be required for verification.	Depends. These kits can be assembled in an FDA or USDA facility. The secondary packaging is not required to have the USDA Mark of Federal Inspection; however, it still can contain the mark. If the secondary packaging does not have the USDA Mark of Federal Inspection, the primary packaging that contains the meat or poultry item must contain the mark.
Pot Pies: Frozen Meat or Poultry	USDA
Product derived from exotic/non-amenable species that contain > 3 percent raw amenable meat	USDA
Products Prepared from Wild Boar from Feral Swine	USDA
Sandwiches[6]: Closed Face Sandwiches (Regardless of the Contents) --Typical "closed-faced" sandwiches consisting of two slices (top and bottom) of cooked grain-based sections that enclose a meat or poultry filling. They are ready-to-serve, hand-held products consisting of, but not limited to the following: Bread, A Bagel, A Biscuit, A Bun, A Croissant, An English Muffin, Pancakes/Hotcakes, Waffles	FDA * Producer can request a voluntary inspection from USDA.
Sandwiches[6]: Closed faced that are cut into wedges, and placed into packaging with the contents displayed (Containing Meat or Not)	FDA * Producer can request a voluntary inspection from USDA, if the sandwich contains meat or poultry.
Sandwiches[8]: Dinners containing a sandwich type product, e.g., a frankfurter, hamburger, or sliced poultry meat with a bun	USDA
Sandwiches: Sliced Egg	FDA
Sandwiches[7]: Open Face Sandwich (If it contains meat or poultry)	USDA
Spaghetti Sauce (>2% meat)	USDA
Stromboli	USDA

[4] Some products that are exempted from USDA jurisdiction based on the criteria above include stocks or broths prepared with "relatively small amounts" of meat or poultry, bouillon cubes, dehydrated meat soups, cheese balls with pepperoni, pork and beans, closed-face sandwiches, mince meat, bagel dogs, and pepperoni rolls. A condition for the application of these exemptions is that product exempt from USDA jurisdiction must still be prepared with USDA inspected meat or poultry product or meat or poultry from an inspection system equivalent to the USDA inspection system. In addition, generally, any product exempted from USDA jurisdiction cannot be represented as a meat food or poultry product, except as provided in the meat or poultry regulations. A product is deemed as representing a meat food or poultry product if a term representing meat or poultry is used on labeling, e.g., in the product name, without appropriate qualification.

[5] FDA jurisdiction as long as the strips of meat in question come bundled in a tortilla.

[6] **Definition of Sandwich - Closed:**
Product must contain at least 35 percent cooked meat and no more than 50 percent bread. Sandwiches are not amenable to inspection. If inspection is requested for this product, it may be granted under reimbursable Food Inspection Service.

Typical "closed-faced" sandwiches consisting of two slices of bread or the top and bottom sections of a sliced bun that enclose meat or poultry, are not amenable to the Federal meat and poultry inspection laws. Therefore, they are not required to be inspected nor bear the marks of inspection when distributed in interstate commerce.

[7] **Definition of Sandwich - Open:**
Must contain at least 50 percent cooked meat. Sandwiches are amenable only if they are open faced sandwiches. Product must show a true product name, e.g., "Sliced Roast Beef on Bread."

This regulatory policy in no way alters the Department's present policy with respect to caterers who include meat sandwiches in their dinners.

[8] **Definition of Sandwich (Meat or Poultry Components of "Dinner Products"):**
Dinners containing a sandwich type product, e.g., a frankfurter, hamburger, or sliced poultry meat with a bun, are amenable and subject to inspection.

How do I know if a meat, poultry or egg products have been inspected by the USDA?

The following Marks of Inspection will be applied to the product.
***The numbers "38", "00" and "42" are examples only. The number changes, depending upon where the inspection was performed.**



MEAT

See 9 CFR 312.2 for further details		See 9 CFR 327.26 for further details	
Livestock Carcasses:	**Finished Products:**	**Import mark stamp on cattle, sheep, swine, and goat carcasses, primal parts, and cuts, not in containers that are offered for entry.**	**Import mark stamp on outside containers of meat and meat food products prepared from cattle, sheep, swine, and goats that are offered for entry.**
			

RABBIT
(Voluntary Inspection)

See 9 CFR 354.65
Inspected and certified edible products


EXOTIC ANIMALS
(Voluntary Inspection)

See 9 CFR 352.7	(See 9 CFR 352.7)
Exotic Carcasses and Parts	**Exotic Carcasses and Parts (mechanically applied)**
	

CUSTOM EXEMPT - MEAT
****CONNOT BE SOLD INTO COMMERCE**

(See 9 CFR 303.1)
Custom Prepared Carcasses and Parts
NOT FOR SALE

POULTRY and RATITES

See 9 CFR 381.96	See 9 CFR 381.204
Carcasses and Parts:	**Import mark stamp on poultry products offered for entry.**
	

EGG PRODUCTS

See 9 CFR 590.413	See 9 CFR 590.940
Egg Products	**Import mark stamp on egg products offered for entry.**
	

What is the definition of amenability?

The Federal Meat Inspection Act (FMIA) and Poultry Products Inspection Act (PPIA), and their implementing regulations, provide for certain exemptions from USDA jurisdiction (and, therefore, inspection), e.g., products prepared for human consumption that contain meat or poultry ingredients in relatively small proportions, or are not considered by consumers to be products of the meat or poultry industry. Generally, the USDA has determined by policy that the "relatively small proportions" of livestock ingredients are: 3 percent or less raw meat; less than 2 percent cooked meat or other portions of the carcass; or 30 percent or less fat, tallow or meat extract, alone or in combination. In the case of poultry, the ?relatively small proportions" are: less than 2 percent cooked poultry meat; less than 10 percent cooked poultry skins, giblets or fat, separately; or less than 10 percent cooked poultry skins, giblets, fat and poultry meat (limited to less than 2 percent) in any combination (refer to 9 CFR 381.15(a)).

For dried products containing poultry, these percentages are computed on the basis of the moist cooked chicken in the ready to serve product when prepared according to the directions on the consumer package. Regarding the second exemption criterion, the USDA has determined the application of the historical perception" criterion to food products containing meat or poultry on a case-by-case basis.

What are the amenable species?
The amenable species are cattle, sheep, swine, goats, horses, mules, other equines, domesticated chickens, turkeys, ducks, geese, guinea, ratites (ostrich, emu and rhea), squabs, and siluriformes (catfish, swai, basa, etc.)

Nonamenable or non-amenable species are exotic species under voluntary inspection.
Examples include bison, domestic rabbits, domestic deer, pheasant, quail, and captive raised waterfowl. Effective September 13, 2021, “exotic animal" means any reindeer, elk, deer, antelope, water buffalo, bison, buffalo, or yak (9 CFR 352.1(k)). The rule also updates the definitions of the other exotic animal classes to better align with current taxonomy. Voluntary inspection is handled under the *Agriculture Marketing Act.*

When is a meat food product considered adulterated?

- Was prepared, packed or held under insanitary conditions;
- is for any reason unsound, unhealthful, unwholesome or unfit for human food;
- consists in whole or part of any filthy, putrid, or decomposed substance;
- may have been rendered injurious to health; or
- bears or contains any poisonous or deleterious substance which may render it injurious to health (i.e. undeclared allergen, chemical residue).

A meat food product is economically adulterated when any valuable constituent, in whole or in part, has been omitted or removed, or in which a less valuable substance has been substituted.
A meat food product is misbranded if its label is false or misleading, or if it does not contain the required labeling features**.**

Can State-inspected products that are not amenable to the Federal Meat Inspection Act or the Poultry Product Inspection Act be transported in interstate commerce?
Perhaps, if in compliance with FDA and State laws and requirements. Food products from non-amenable species (e.g., bison, quail) fall under the jurisdiction of the Food and Drug Administration (FDA). FDA-regulated products may move in interstate commerce in accordance with FDA regulations. States can require that non-amenable species receive State inspection. However, State or voluntary FSIS inspection does not alter the species amenability as it relates to the FMIA, PPIA or FSIS regulations. Thus, interstate movement of State-inspected or voluntary FSIS-inspected non-amenable product will be dictated by FDA and State laws and requirements.

Who inspects egg products?
Since 1995, the Food Safety and Inspection Service (FSIS) of the United States Department of Agriculture (USDA) has been responsible for the inspection of egg products. In 1970 Congress passed the Egg Products Inspection Act (EPIA), which provides for the mandatory continuous inspection of the processing of liquid, frozen, freeze dried, dried egg products and egg substitutes.

From 1970 to 1995 the Poultry Division of USDA's Agricultural Marketing Service inspected egg products. FSIS inspects all egg products, with and without added ingredients, with the exception of those products exempted under the Act. Officially inspected egg products will bear the USDA inspection mark. The Department of Health and Human Services' Food and Drug Administration is responsible for the inspection of imitation eggs, and similar products which are exempted from continuous inspection under the EPIA.

What are the exemptions from USDA FSIS inspection?
The FMIA, in 21 U.S.C. 623(a), exempts from routine Federal inspection:

- Livestock slaughtered for personal use
- Livestock custom slaughtered or prepared


The FMIA, in 21 U.S.C. 661(c)(2), exempts from routine Federal inspection, operations of types traditionally and usually conducted at:

- Retail stores
- Restaurants
- Restaurant central kitchen facilities
- Caterers


Determining Livestock slaughter exemptions

How do I determine if I am eligible for one of these exemptions?

In order to determine whether your livestock slaughter or meat processing operation qualifies for an exemption from the Federal Meat Inspection Act, ask yourself the question in the bold type and then follow the appropriate Yes or No response arrow.



In order to determine whether your retail, restaurant, central kitchen or catering operation qualifies for an exemption from the Federal Meat Inspection Act, ask yourself the question in the bold type and then follow the appropriate response arrow.



[1] Must start with inspected and passed product or raw product prepared at a retail exempt store


Poultry Exemptions

The term "exempt" means that certain types of poultry slaughter and processing operations qualify to operate without the benefit of Federal inspection on a daily basis, and a grant of Federal inspection is not required. However, the Poultry Products Inspection Act (PPIA) does not exempt any person slaughtering or processing poultry from the provisions requiring the manufacturing of poultry products that are not adulterated and not misbranded.

Exempt slaughtered poultry or poultry products cannot be sold, offered for sale, transported, or offered for transportation between States, a.k.a. via interstate commerce.

Poultry exempt operators are required to operate and be maintained in a manner that prevents the creation of insanitary conditions and ensures that the product is not adulterated. Sanitary requirements can be found under the PPIA Section 464(c)(2); Title 9 CFR 381.10(a)(7) and 416.2-416.5 and the Food Safety Inspection Service's (FSIS) *Sanitation Performance Standards Compliance Guide,* dated October 13, 1999.

If your operation qualifies for a specific exemption, no deviations of the parameters of that specific exemption may occur for one calendar year, after your choice is made. You will not be authorized to change between the varying exemptions when the same calendar year.



Summary of Table of Exemptions and Limitations - Poultry								
Criteria	**Personal Use**	**Custom**	**Producer Grower – 1,000 Bird Limit**	**Producer Grower – 20,000 Bird Limit**	**Producer Grower or Other Person**	**Small Enterprise 20,000 Bird Limit**	**Retail Dealer**	**Retail Store**
Slaughter Limit	NONE	NONE	YES 1,000	YES 20,000	YES 20,000	YES 20,000	YES ZERO	NONE
Processing	YES	YES	YES	YES	YES	CUT UP ONLY	CUT UP ONLY	YES
75 lb. Sale Limit to Consumer	NO SELLING	NO SELLING	NO LIMIT	NO LIMIT	NO LIMIT	NO LIMIT	NO LIMIT	YES
150-lb. Limit to HRI	NO SELLING	NO SELLING	NO LIMIT	NO LIMIT	NO LIMIT	NO LIMIT	NO LIMIT	YES
25% of Total product/75 % HRI Sale	NO SELLING	NO SELLING	NO LIMIT	NO LIMIT	NO LIMIT	N/A	YES	YES
Can Sell to any Customer	NO	NO	YES	YES	NO	YES	NO	NO
Can Sell to HRI	NO	NO	YES	YES	NOT TO ALL HRI[1]	YES	YES	YES
Sell to Distributor	NO	NO	YES	YES	YES	YES	NO	NO
Sell to Retail Store	NO	NO	YES	YES	NO	YES	NO	NO
Intra-State Distribution	NO	NO	YES	YES	YES	YES	YES	YES
Inter-State Distribution	NO	NO	NO	NO	NO	NO	YES[2]	NO[2]

[1] Product produced under the Producer/Grower or Other Person Exemption may not be sold to institutions.

[2] Only poultry products derived from federally inspected and passed poultry may be transported in interstate commerce.

Table of Exemptions and Limitation - Poultry

EXEMPTION	Customer(s) that the exempted poultry may be sold to.	Limitations: 1. on amount poultry product produced under the exemption 2. 25% or less exempt sales to HRIs 3. calendar year total sales dollar limitation 4. Identification/labeling requirements	Type of operations exempt: 1. Slaughter, 2. Processing, 3. Cut-up only.
Personal Use	Personal Use exempt poultry products may not be sold or donated for use as human food to any customer or consumer. The poultry is for the exclusive private use of the owner	1 – No limit 2 & 3 – No sales of poultry permitted 4 – The statement "Exempt P.L. 90-492" and producer's name and address on shipping contains	1. Slaughter 2. Processing.
Custom Slaughter/ Processing	Custom Slaughtered exempt poultry products may not be sold or donated for use as human food. A custom slaughter may not engage in the business of buying or selling poultry used for human food	1 – No limit 2 & 3 – No sales permitted 4 – The statement "Exempt P.L. 90-492" and the producer's name and address on shipping containers.	1. Slaughter, 2. Processing other person's poultry.
Producer Grower 1,000 bird limit	Limited Provision of the Act apply May sell to any person, must keep records -of sales (Title 9 CFR 381.175)	1 – Yes, no more than 1,000 poultry in calendar year. Of their own raising on their own farm	1. Slaughter 2. Processing of poultry grower's raised poultry for sale to customers.
Producer Grower 20,000 bird limit	Slaughters & processes on his/her premises poultry for distribution by him/her to any person The product may only be distributed in the State, territory, or DC where it was prepared	1 – Yes, may slaughter and process no more than 20,000 poultry in calendar year of their raising on their own premises. 2 – 25% HRI limitation **does not** apply 3 – Dollar limitation **not** applicable. 4 – The statement "Exempt P.L. 90-492" and producer's name and address on product when it is distributed.	1. Slaughter & 2. Processing of poultry grower's raised poultry.
Producer Grower or Other Person (PGOP)	Slaughters & processes poultry for distribution to only household consumers, restaurants, hotels, or boarding houses. The exempt product may only be distributed in the State, territory, or District of Columbia where it is prepared.	1 – Yes, no more than 20,000 poultry in calendar year. 2 &3 not applicable. 4 – The statement "Exempt P.L. 90-492" and producer's name and address are required on product when it is distributed. 5 – May not slaughter or process poultry at a facility used for slaughtering or processing by another person.	1. Slaughter 2. Processing of raised or purchased (live) poultry
Small Enterprise	No restrictions on type of customer A small enterprise may not use or distribute products from, PGOP, Retail Dealer, or Retail Store exemptions The exempt product may only be distributed in the State, territory, or DC where it is prepared.	1 – Yes no more than 20,000 poultry in a calendar year. 2 &3 --not applicable. 4 – All the features of an official label when distributed, with the exceptions that the official inspection legend cannot be used, modification of the safe handling instructions and the nutrition facts are optional, provided, the labeling does not bear nutrition or health claims. 5 – May not slaughter or process poultry at a facility used for slaughtering or processing by another person.	1. Slaughter 3. **Cut-up only**
Retail Dealer	Sales limited to household consumers, hotels, or restaurants, or similar institutions. Sales to household consumers in store must be 75% of total sales. Sales to retail markets or distributors disqualify an establishment form a Retail Exemption. Product prepared from poultry previously inspected and passed by USDA permitted to cross Stateline, move in "Commerce."	1 – No limit on pounds sold to consumers. 2 – 25% **HRI limitation applies** 3 – Dollar limitation **not** applicable. 4 – All the features of an official label, with the exceptions that the official inspection legend cannot be used, modification of the safe handling instructions and the nutrition facts are optional, provided, the labeling does not bear nutrition or health claims.	1. No Slaughter. 3. Processing limited to cutting up of previously UDSA Inspected and Passed Poultry
Retail Store	Sales limited to household consumers, hotels, or restaurants, or similar institutions. Sales to household consumers in store must be 75% of sales. Sales to retail markets or distributors disqualify an operation from a Retail Store exemption. Product prepared from product previously inspected and passed by USDA permitted to cross Stateline, move in "Commerce "Other, exempt product may only be distributed in the State, territory, or DC where it is prepared.	1 – Yes, there is a limit of 75 lbs. for household sales and a 150 lbs. limit for HRI sales. 2 – **25% HRI limitation does apply** 3 – Dollar limitation applicable.	1. Slaughter of live poultry purchased by consumer at the retail store and processed by the retail store operator in accordance with the consumer's instructions. 2. Processing

Annual Dollar Limitations for Retail Store Sales to HRI

How is industry notified of adjustments to the dollar limitations on the amount of meat and meat food products, including Siluriformes fish and fish products, and poultry and poultry products that a retail store can sell to hotels, restaurants, and similar institutions (HRI) without disqualifying itself for exemption from Federal inspection requirements?

Industry is notified of the annual dollar limitations by a notice published in the Federal Register and through the Constituent Update. The current dollar limits for calendar year 2022 can be found in the Federal Register Notice at Retail Exemptions Adjusted Dollar Limitations [FSIS-2023-0007] .

In addition, the FSIS website email subscriptions allows subscribers to sign up and receive email alerts on numerous topics, including the publication of documents in the Federal Register.

What is the FSIS policy regarding the preparation of meat products for sale to other than household consumers by retail stores?

FSIS' policy regarding whether the preparation of meat products for sale to other than household consumers by a retail store is exempt from inspection is based on what operation is employed in preparing the product, and where that operation falls under 9 CFR 303.1 (d) (2) (iii) (f). If the retail store engages in the operations of cutting up, slicing, and trimming of carcasses, halves, quarters, or wholesale cuts into retail cuts such as steaks, chops, and roasts, and freezing such cuts; grinding and freezing products made from meat; breaking bulk shipments of products; or wrapping or rewrapping such products in the preparation of retail products for sale to other household consumers, it would be exempt from inspection. 9 CFR 303.1 (d) (2) (iii) (f). The retail store would also have to make no more than 25% of its sales to other than household consumers, and its sales to other than household consumers could not exceed the dollar limits on such sales that FSIS establishes. 9 CFR 303.1 (d) (2) (iii) (b).

If a retail store cures, cooks, renders, refines livestock fat, or engages in other operations to prepare products for other than household consumers, then those operations are subject to inspection, regardless of the percent of its sales that are to other than household consumers or of the dollar amount of those sales. 9 CFR 303.1 (d) (2) (iii) (f).

Additional Information regarding the Agency policy:

This policy flows in a straightforward and direct way from the Agency's regulations. There is significant confusion, however, when the question about the Agency's policy focuses not on the operation employed in preparing the product, but on what goes into the product. In a letter in 2004, Philip Derfler, Assistant Administrator, OPPED (now OPPD), stated to Art Marquez of the State of New Mexico that the preparation of a multi-component meat product by a retail store for other than household consumers would not be covered by the retail exemption and would be subject to inspection. This letter has been interpreted to mean that the preparation of any multi-ingredient product for non-household consumers by a retail store would subject the store to inspection, including, for example, a grinding process in which a seasoning is added to the meat that is ground.

OPPD has received numerous inquiries as to whether this interpretation of the limits of the coverage of the retail exemption is correct. In response to these inquiries, OPPD has reconsidered the interpretation of 9 CFR 303.1 (d) set out in Mr. Derfler's letter. After careful consideration of the letter, the regulation, related regulations, and the Federal Meat Inspection Act, OPPD has concluded that the interpretation in Mr. Derfler's letter to Mr. Marquez is not supportable.

Tying the preparation of a multiple component meat product, regardless of what components go into that product, to the exemption from inspection is not consistent with the principle for determining the coverage of the exemption that is embodied in 9 CFR 303.1 (d). On the face of that regulation, the factor that determines whether the exemption applies is the nature of the operation used in preparing the product, not food composition. See 9 CFR 303.1 (d) (2) (i). Grinding is listed in 9 CFR 303.1 (d) (2) (i) (b) and, under 9 CFR 303.1 (d) (2) (iii) (f), is one of the operations that would remain subject to the retail exemption even if used in the production of product for non-household consumers. Mr. Derfler's letter would create an exception to the regulation if the grinding is of a multi-component product, but there is nothing in 9 CFR 303.1(d) that would provide a basis for such an exception.

It makes sense to focus on the operation used in preparing a meat product in deciding whether inspection is required. The operation will have a definitive effect on the nature of the product, and there is a need to verify that nothing that will affect the safety or wholesomeness of the food occurs in the performance of the operation. The addition of a component or an ingredient may not have such a definitive effect. For example, the addition of a curing agent to Italian sausage would affect the nature of the sausage, as well as its safety, and the modified

sausage would need to be named to reflect the fact that it is cured. See 9 CFR 319.145. However, the addition of other ingredients for the purpose of seasoning would have no effect on the nature or safety of a meat product. The addition of seasoning to beef that is ground, for example, would not affect the nature of the meat product. The product would still be ground beef. See 9 CFR 319.15. Thus, because the addition of an ingredient (component) would not necessarily have an effect on the nature of a meat product, there is no logical reason why this factor should be determinative of whether the preparation of the product at a retail store for a non-household consumer is exempt or subject to inspection.

An argument may be made, however, that the use of the words "preparation of products" in 9 CFR 303.1 (d) (2) (i) (c) was intended to cover the preparation of multi-component products. In the Federal Meat Inspection Act itself, "prepared" is defined as "slaughtered, canned, salted, rendered, boned, cut up, or otherwise manufactured or processed." The argument in support of the interpretation in Mr. Derfler's letter would be that putting together a multi-ingredient product would come within the "otherwise manufactured" part of this determination. However, the definition of "prepared" in the statute includes operations that cannot be performed at retail such as slaughter. Therefore, this definition cannot be used to decide how to interpret 9 CFR 303.1 (d) (2) (i) (c).

A more straightforward interpretation of the phrase "preparation of products" in 9 CFR 303.1 (d) (2) (i) (c) is that it is intended to be a catchall that covers any operation not otherwise listed in 9 CFR 303.1 (d) (2) (i). Interpreted in this way, the phrase would not convey any special status to multi-ingredient products. The grinding of multi-ingredient products at retail for non-household consumers would be covered by 9 CFR 303.1 (d) (2) (i) (b) and thus would be exempt from inspection.

Thus, Mr. Derfler's letter is not supported by the Agency's regulations and is hereby withdrawn and declared to be without force or effect. To reiterate, FSIS' policy regarding whether the preparation of products for sale to other than household consumers by a retail store is exempt is that the question is to be resolved based on what operation is employed in preparing the product, and where that operation falls under 9 CFR 303.1 (d) (2) (iii) (f).

Can livestock or poultry slaughtered and processed under the personal-use exemption or the custom-exemption be donated?
No, 21 USC 464(c) and §623(a) limit personal-use and custom-exempt meat and poultry product as exclusively for the individual product owner, for use in the household of such person, by him and members of his household and his non-paying guests and employees.

Are private warehouses and custom exempt operators required to submit FSIS Form 5020-1 Registration of Meat and Poultry Handlers? In other words, are these two types of businesses required to register with FSIS?
No. Neither the Federal Meat Inspection Act (FMIA), Section 203 (21 U.S.C. § 643) nor the Poultry Products Inspection Act (PPIA), Section 11(c) & (d) (21 U.S.C. § 460) require these specific business types to register with Food Safety Inspection Service (FSIS). However, the FMIA and PPIA do require that persons, firms, or corporations engaged in business, in or for commerce as a broker, renderer, animal food manufacturer, OR a wholesaler of meat or poultry products, OR public warehouse operators storing such products in or for commerce, OR buying, selling, or transporting dead, dying, disabled or diseased poultry or livestock, register with FSIS. Private warehouses, unlike public warehouses, are entities that exclusively store their own product for distribution to their retail stores. Businesses engaging in the slaughter or preparation of custom exempt product (which is not eligible for sale), and businesses storing their own product, strictly for distribution to their own retail outlets, without any wholesale sales, do not fall under any of the business types required by the FMIA and PPIA to register with FSIS.

Where can I find information and regulations for transporting livestock across state lines?
The interstate movement of livestock is regulated by the individual state receiving the animals, although the United States Department of Agriculture (USDA) has the authority to regulate interstate transport in relation to particular disease concerns or when an animal health emergency has been declared. Information about state regulations can be found here: State Regulations for Importing Animals. For further information, we recommend that you contact the State Veterinarian/animal health official for your state. Contact information is available at State Animal Health Officials.

Is it legal to sell wild game meat?
There is no law prohibiting the sale of wild game meat (venison, etc.). There are, however, laws prohibiting the sale of uninspected wild game meat. If wild game meat has received a mark of inspection by a state or federal inspection program, or it has been legally imported, then its sale is legal anywhere within the United States. Game meats that do not have a mark of inspection cannot be sold. This is the case for game meat harvested by a recreational hunter. The inspection and processing requirements will not be met, and the meat cannot be sold.

Meat from "game animals" as defined by state wildlife agencies that are harvested within that state cannot be sold. The restrictions and definitions vary from state to state. However, in most states native species (like whitetail deer) are deemed to be "game animals" while non-native species have different classifications, usually deemed "livestock." If it is restricted, then it will not be inspected and cannot be sold. However, if it is inspected then that is assurance that it is legal to sell.

What are cottage foods, IAW Idaho Law?
Cottage foods are foods made in a person's home or other designated location and sold directly to a consumer. They include foods that are defined in the Idaho Food Code as non-Time/Temperature Control for Safety (non-TCS) foods. Examples of cottage foods include: baked goods that do not require refrigeration, fruit jams and jellies, honey, fruit pies, breads, cakes that do not require refrigeration, pastries and cookies that do not require refrigeration, candies and confections that do not require refrigeration, dried fruits, dry herbs, seasonings and mixtures, cereals, trail mixes and granola, nuts, vinegar and flavored vinegars, popcorn and popcorn balls, or tinctures that do not make medicinal claims.

What are some of the more important Statues, Regulations or Guidelines that helps me understand where the rules or lines drawn?
Statues:
The Federal Meat Inspection Act - 21 U.S.C. 601 et. seq

The Poultry Products Inspection Act - 21 U.S.C. 451 et. seq

The Egg Products Inspection Act - 21 U.S.C. 1031 et. seq

The Humane Methods of Slaughter Act - 7 U.S.C. 1901 et. seq.

Regulations:

9 Code of Federal Regulations (CFR) 300-599

Guidelines:

Guidance for Determining Whether a Poultry Slaughter or Processing Operation is Exempt from Inspection Requirements of the Poultry Products Inspection Act

FSIS Guideline for Determining Whether a Livestock Slaughter or Processing Firm is Exempt from the Inspection Requirements of the Federal Meat Inspection Act

Investigations Operations Manual, 2022: Exhibit 3-1: FDA/USDA Jurisdiction

FSIS's Food Standards and Labeling Policy Book

Exhibit E10:

Archived: Monday, May 4, 2026 1:13:33 PM
From: Keaton Massie
Mail received time: Fri, 1 May 2026 15:02:35
Sent: Fri, 1 May 2026 15:01:51
To: Michael Stowell Amber Lewter Amber Lewter
Subject: [External] Re: CU2025-0031
Importance: Normal
Sensitivity: None
Attachments:
R39357012 Response Times 2.pdf R39357012 Response Times.pdf

Hello Amber!

Chief Stowell asked that I respond to this email. I have created a response time map for this parcel. https://arcg.is/1LKvbr3 For convenience, I also have attached two PDFs that show the response times. I believe this particular parcel lies in Parma Fire District and they would have a faster response time then us.

Please let me know if you have any questions!

Thank you,
Capt. Keaton Massie

From: Michael Stowell <mstowell@ccparamedics.com>
Sent: Tuesday, April 28, 2026 1:01 PM
To: Keaton Massie <kmassie@ccparamedics.com>
Subject: FW: CU2025-0031


From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Tuesday, April 28, 2026 12:44 PM
To: Michael Stowell <mstowell@ccparamedics.com>
Subject: CU2025-0031

Hello,


Could you please provide me with the response times to parcel R39357012?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605


25.020711198
28.29724101
27.0962116
27.0962116
28.29724101
25.020711198
Jenness
Sand Hollow
West Hartley Gulch
Emmett Valley
Roswell
Arena Valley
Peckham Rd
Doles
McIntyre Hill
M53
M52
M51
Hwy 44
84
30
95
20
Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, (c) OpenStreetMap contributors, and the GIS User Community, Esri, NASA, NGA, USGS

R39357012 Response Times



5/1/2026

Route 1 - 1 - 1

Route 1 - 1 - 1

Route 1 - 1 - 1

M53 station

M52 station

M51 station

R39357012 Response Times

World_Hillshade

1:278,207

0 1.75 3.5 7 mi

0 2.75 5.5 11 km

Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, (c) OpenStreetMap contributors, and the GIS User Community, Esri, NASA, NGA, USGS

Exhibit E11:


Archived: Monday, May 4, 2026 5:14:41 PM
From: Jeff Rodgers
Mail received time: Mon, 4 May 2026 23:07:58
Sent: Monday, May 4, 2026 5:07:59 PM
To: Amber Lewter ParmaRuralFire@gmail.com
Subject: Re: [External] Re: CU2025-0031
Importance: Normal
Sensitivity: None

It would be about 5 mins just drive time from the city of Parma

Sent from my T-Mobile 5G Device
Get Outlook for Android

From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Monday, May 4, 2026 2:31:47 PM
To: Jeff Rodgers <jeff@parmafire.us>; ParmaRuralFire@gmail.com <ParmaRuralFire@gmail.com>
Subject: RE: [External] Re: CU2025-0031

Yes of course! The address is 0 Hwy 95, Parma, ID, 83660



Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov
Website: www.canyoncounty.id.gov

Development Services Department (DSD)
Public office hours
Monday, Tuesday, Thursday and Friday
8am – 5pm
Wednesday
1pm – 5pm
**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

From: Jeff Rodgers <jeff@parmafire.us>
Sent: Monday, May 4, 2026 1:22 PM
To: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>; ParmaRuralFire@gmail.com
Subject: [External] Re: CU2025-0031

Can I get an address I'm unable to look up a parcel number

Sent from my T-Mobile 5G Device
Get Outlook for Android

From: Amber Lewter <Amber.Lewter@canyoncounty.id.gov>
Sent: Monday, May 4, 2026 12:59:17 PM
To: ParmaRuralFire@gmail.com <ParmaRuralFire@gmail.com>
Cc: Jeff Rodgers <jeff@parmafire.us>
Subject: RE: CU2025-0031

Hello,

I am following up on my request. May I please get the response times?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov

Website: www.canyoncounty.id.gov

Development Services Department (DSD)
Public office hours
Monday, Tuesday, Thursday and Friday
8am – 5pm
Wednesday
1pm – 5pm
**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

From: Amber Lewter
Sent: Tuesday, April 28, 2026 12:42 PM
To: 'ParmaRuralFire@gmail.com' <ParmaRuralFire@gmail.com>
Subject: CU2025-0031

Hello,

Could you please provide me with the response times to parcel R39357012?

Thank you,

Amber Lewter
Associate Planner
Canyon County Development Services Department
111 N. 11th Ave., #310, Caldwell, ID 83605

Direct Line: 208-454-6631
Email: amber.lewter@canyoncounty.id.gov
Website: www.canyoncounty.id.gov

Development Services Department (DSD)
Public office hours
Monday, Tuesday, Thursday and Friday
8am – 5pm
Wednesday
1pm – 5pm
**We will not be closed during lunch hour **

PUBLIC RECORD NOTICE: All communications transmitted within the Canyon County email system may be a public record and may be subject to disclosure under the Idaho Public Records Act and as such may be copied and reproduced by members of the public.

Exhibit F:

EXHIBIT F

Public Comments Received by: May 11, 2026

Planning & Zoning Commission

Case #: CU2025-0031

Hearing Date: May 11, 2026

Exhibit F1:

GROWING TOGETHER

Growing Together LLC
301 Warehouse St.
Caldwell, ID 83605

Date: April 27, 2026

Canyon County Planning and Zoning Commission
Canyon County Development Services
111 N. 11th Ave., Suite 203
Caldwell, ID 83605

Re: Letter of Support for the Hansen Slaughterhouse and Butcher Shop Application

Commissioners:

Growing Together LLC respectfully submits this letter in support of the proposed Hansen slaughterhouse and butcher shop.

CCZO § 07-10-25(1) states that the purposes of the Agricultural zone include encouraging the protection of viable farmland and farming operations and protecting agricultural land uses from unreasonable adverse impacts from development. This proposal supports working agriculture by providing a service directly tied to livestock production rather than displacing agricultural use.

CCZO § 07-10-27 identifies a food processing facility as a conditional use in the Agricultural zone. That is important because it shows the zoning ordinance expressly contemplates this type of agriculturally related processing use in the Agricultural zone, subject to site-specific review and approval through this CUP process.

Comprehensive Plan Policy 4.05.00 directs Canyon County to maintain agriculture as the principal land use in the County and ensure land use and planning decisions support a robust agricultural economy. Policies 3.05.00 through 3.05.03 further support increasing agricultural-based businesses, building Canyon County as a premier location for agricultural-based businesses, restricting business development in agricultural zones to uses directly related to agriculture, and allowing facilities that support ag-business. A local slaughterhouse and butcher shop is consistent with those policies because it provides needed meat processing services for local producers and helps strengthen the agricultural economy.

Comprehensive Plan Policy 11.04.03 and 11.04.03A support the growth, expansion, and diversification of Canyon County's agricultural industries, including agriculturally related industries

such as food processing. The proposed facility is consistent with that direction and is also expected to create local jobs and provide a more direct market outlet for livestock producers.

Comprehensive Plan Policies 4.05.01 and 4.05.02 support conserving agricultural land and protecting the integrity of agriculture. Based on the description provided, this project appears to involve relatively minimal site disturbance and appears more compatible with the agricultural character of the area than many nonagricultural uses.

CCZO § 07-10-03(1) requires each parcel to demonstrate adequate access for equipment, emergency vehicles, and other services before issuance of a certificate of zoning compliance. For that reason, access should be clearly confirmed to ensure safe and appropriate routes for customers, deliveries, and emergency response.

For these reasons, Growing Together LLC supports this application, subject to confirmation of safe and adequate access, because it appears consistent with the Agricultural zone, the conditional use framework of the zoning ordinance, and the Comprehensive Plan's policies supporting agricultural viability and agricultural-based business.

Thank you for your consideration.

Sincerely,

George Crookham
President, Growing Together LLC

Growing Together (GT) LLC

Mission Statement: To improve citizens' knowledge of local land use planning and to support good economic land use decisions.

cc. Growing Together Advisory Board

Exhibit F2:

Mike and Charlie Sety
4629 N. Mountain View Dr.
Boise, ID 83704
[redacted]

May 8, 2026

Canyon County Development Services Department
Attn: Amber Lewter
111 North 11th Avenue, Ste 310
Caldwell, ID 83605

RE: Case No. CU2025-0031, Lucus Hansen requesting a Conditional Use Permit for a Slaughterhouse on 11.3 acres and retail sales near 32925 Highway 95, Parma, ID

We are the owners of an adjacent agricultural property located near 32925 Highway 95 near Parma. We are writing to formally object to the proposed Conditional Use Permit for the slaughterhouse on the neighboring 11-acre parcel. While we support agriculture in Canyon County, this proposal represents a significantly more intensive use that creates substantial conflicts with the surrounding agricultural operations and shared infrastructure.

1) It is a risk to irrigation water and agricultural viability. The subject property is bordered on the north and west by an irrigation ditch (Farmers' Co-Operative Ditch Co) that serves surrounding farmland. A slaughterhouse generates organic waste, including blood and processing byproducts, which pose a contamination risk if not properly contained. Any failure, overflow, or runoff event could impact irrigation water relied upon by neighboring agricultural properties, including mine. The application does not sufficiently demonstrate how wastewater, storm water, and accidental discharges will be prevented from entering the adjacent irrigation system. This raises serious concerns regarding compliance with water quality protections and the long-term viability of nearby operations.

2) It is incompatible with adjacent agricultural use. Although located in an agricultural area, a slaughterhouse is materially different from typical crop production. Odor, airborne particles, and waste-related byproducts can negatively affect farming conditions, workers, and the usability of the adjacent land. This proposal introduces industrial-scale impacts into an area currently used for traditional agriculture, creating a conflict rather than compatibility.

3) It is an inadequate parcel size and buffering. At only11 acres, the parcel does not provide sufficient space to buffer neighboring properties from odor, noise, and operational impacts. As an immediately adjacent landowner, our property will be directly exposed to these effects without possible meaningful mitigation.

4) It creates traffic and access concerns. The project will introduce livestock transport and heavy commercial vehicle traffic along US Highway 95. Increased truck traffic, including turning movements and slow moving vehicles, raises safety and operational concerns for the surrounding area.

5) It fails to meet the comprehensive plan standards. The Canyon County Comprehensive Plan requires that conditional uses protect natural resources, including water systems and avoid undue impacts on neighboring properties.

For these reasons, we respectfully request that the Canyon County Planning and Zoning Commission deny the conditional use permit request. At a minimum, the applicant should be required to provide substantially more detailed engineering, environmental safeguards and buffering measures before any approval is considered.

Very truly yours,

Mike Sety & Charlie Sety

Mike and Charlie Sety
4629 N Mountain View Dr.
Boise, ID 83704
[redacted]

Exhibit F3:

Archived: Tuesday, May 12, 2026 10:13:12 AM
From: Jennifer McClain
Mail received time: Mon, 11 May 2026 21:24:52
Sent: Mon, 11 May 2026 15:24:25
To: Amber Lewter
Subject: [External] Adamently Opposed against Case #CU2025-0031
Importance: Normal
Sensitivity: None

Jennifer McClain
28282 Grandview Road
Parma, Idaho 83660
[redacted]

11th May 2026

Amber Lewter
Canyon County Development Services Department
111 N. 11th Avenue #310
Caldwell, ID 83605

Dear Ms. Lewter,

It has very recently come to my attention that there are plans in the works to build a slaughterhouse (#CU2025-0031) in direct line of sight from my front door. I am adamantly opposed to the idea of this building development in my rural neighborhood for the primary reasons air and noise pollution, increased traffic.

First of all, I have lived at 28282 Grandview Road since December of 2021. One of the primary reasons I have enjoyed living here for the last four and a half years is because of the clean air. If this slaughterhouse is in function, I know that the nice clean air that I enjoy will be replaced with the rancid smell of death. Anyone that has passed by and smelled the smell of a feed lot knows what this smell is like. It is a terrible olfactory experience.. . The owner's home is up on a hill above this slaughterhouse. It will always be downwind from him, so why would he be concerned with this factor?

Secondly, the reason I am adamantly opposed to a slaughterhouse that is in close proximity to my home is because of the additional noise pollution it will bring to my personal sanctuary. Working in my garden or sipping ice cold lemonade on my front porch swing will no longer be as enjoyable if I have to hear the machinery noise of a slaughterhouse as background noise.

As anyone knows, when there is a new business anywhere, there is always more traffic. Where there is more traffic, there is more population flow, and where there is more population flow, there is always inevitably more crime. That is common knowledge. It doesn't have to be proven. It already has been proven time and time again.

The reason most of us live here right off HWY 95 in the rural community of Parma is for the peace and quiet, the sanctuary, from the roar of a big city that is chock full of air pollution, noise pollution, and excess traffic. This is not how we would like our neighborhood to be, as it would no longer be a sanctuary. I strongly call for the rejection of case #CU2025-0031. To build a slaughterhouse in direct sight of my front door goes against every reason I chose to live at 28282 Grandview Road in Parma, Idaho.

Sincerely,

Jennifer Ann McClain

Exhibit F4:

Richard and Sheila Hartshorn
28251 Grandview Rd.
Parma, ID 83660
[redacted]

May 11, 2026

Canyon County Development Services Department
Attn: Amber Lewter
111 North 11th Avenue, Ste 310
Caldwell, ID 83605

RE: Case No. CU2025-0031, Lucas Hansen requesting a Conditional Use Permit for a Slaughterhouse on 11.3 acres and retail sales near 28251 Grandview Rd, Parma, ID

We are the owners of property located at 28251 Grandview Road, near Highway 95, Parma ID. We are writing to formally object to the proposed Conditional Use Permit for the slaughterhouse on the neighboring 11-acre parcel. While we support agriculture in Canyon County, this proposal represents a significantly more intensive use that creates substantial conflicts with the surrounding agricultural operations and shared infrastructure.

We believe this project would negatively affect the health, safety, environment, and quality of life of local residents. Our concerns include, but are not limited to:

Odor and air pollution
Increased truck traffic and noise
Potential water and soil contamination
Negative impacts on nearby homes
Concerns regarding public health and sanitation
Decreased property values
Animal welfare concerns

Our neighborhood is not an appropriate location for an industrial slaughterhouse facility. We urge local officials and planning authorities to reject any rezoning requests, permits, or approvals associated with this project.

We respectfully request that decision-makers prioritize the well-being of residents and deny the conditional use permit request and pursue alternative forms of economic development that are more compatible with our community.

Very truly yours,

Richard and Sheila Hartshorn

Richard Hartshorn

Sheila Hartshorn

Exhibit F5:

To: Canyon County Land Use Board 05/11/2026

Subject: Conditional Use Permit # 2025-0031

From Kevin Olinger

It is with much angst I submit not only the following, but a follow up verbal attestment to the opposition of said CUP.

Objections to establishing a slaughterhouse or animal processing facilities in areas not zoned for it or where zoning is contested, (such as residential, rural-residential, or protected environmental zones) frequently center on environmental degradation, devaluation of property, and significant disruption to the quality of life.

Common objections and concerns raised in community, zoning, and legal proceedings include:

1. Environmental & Public Health Risks

- **Water Contamination:** Slaughterhouses generate significant wastewater, often containing high levels of nitrogen, phosphorus, blood, fat, and pathogens like *E. coli*. Concerns are severe in areas with residential wells, where runoff can contaminate the water table.
- **Air Pollution & Odor:** Odors are a major concern, often described as "putrid" and related to, blood, fat, and entrails. Pervasive odors described as “rotting meat/carcasses”. Potential air quality issues include noxious emissions from wastewater lagoons or rendering processes.
- **Waste Management:** Concerns often exist regarding where waste from high-risk materials (such as those associated with bovine spongiform encephalitis, or "mad cow disease") will be disposed of, particularly if local infrastructure cannot handle it. Leaks from tanks, overflowing sewage, improper disposal of manure and by-products.

2. Community & Residential Impacts

- **Noise Pollution:** Constant noise is expected from livestock (crying/screaming), large transport trucks, and machinery, disrupting quiet rural or residential life.
- **Traffic Congestion:** Increased heavy truck and livestock trailer traffic on rural or residential roads is a major concern, causing safety issues and congestion.
- **Property Value Depreciation:** Studies and resident reports frequently cite that slaughterhouses significantly decrease the value of nearby residential properties. Living next to a putrid stink bomb.
- **Quality of Life/Nuisance:** Odor, noise, and visual impact are frequently categorized as a "public nuisance". The erasure of views of open agricultural land now gone. It is to the benefit of whom?

3. Land Use & Zoning Objections

- **Violation of Zoning Laws:** A primary objection is that the facility is not permitted in the county's current, intended, or master-planned land use for that area.

- **Inappropriate Location:** Residents often argue that such industrial operations belong on properly zoned industrial land, rather than near schools, residential subdivisions, or in areas with high-water tables.
- **Spot Zoning:** Allegations that the council or zoning board is giving “Special Treatment” to a specific/particular applicant.
- **Fear of Expansion:** Concerns that a small-scale, locally focused operation will inevitably expand beyond its promised scope, increasing the environmental and social impacts.

4. Animal Welfare and Social Concerns

- **Humane Handling Concerns:** Concerns regarding the treatment of livestock on-site, particularly if the operation is small and lacks frequent, direct government inspections.
- **Emotional Distress:** Exposure of residents, particularly children, to the sights and sounds of animal slaughter.

Common Legal/Administrative Tactics to Oppose

- **Documenting Zoning Violations:** Using the violation of zoning laws to obtain a cease and desist order from the county’s Department of Planning.
- **Nuisance Lawsuits:** Filing suits based on the "unreasonable interference" with the enjoyment of property (noise, odor, traffic).
- **Environmental Petitions:** Requesting studies from environmental agencies (like the DEQ) regarding potential contamination of waterways and ground water tables.
- **Challenging "Conditional Use Permits":** Challenging the issuance of special permits that would allow a forbidden use in an area is appropriate for good governance.

Operational and Safety Concerns

Improper Storage/Handling:

Residents may raise concerns about the sight of animal carcasses being transported or stored in open view.

Over-expansion:

Fear that a small, initially approved , small-scale facility will expand into a larger scale industrial operation.

Lack of Oversight:

Concerns about who is responsible if the operator fails to manage waste properly.

In cases where these facilities were proposed in unpermitted areas, opposition has included lawsuits arguing that the governmental approvals were not supported by evidence or by launching petitions to force legal intervention on behalf of those affected/effected.

It is with the above information concerning said endeavor I end this letter of opposition and will follow up in person.

Please take a look at included info at the following website: 

BREAKING: Silsbee council votes against ordinance that ...



KFDM
https://kfdm.com › news › local › silsbee-debates-ordina...

Exhibit F6:

Petition Opposing the Construction of a Slaughterhouse in the area of Hwy 95 between Pearl and Grandview Road in Parma, Idaho.

To: County Commissioners / Planning & Zoning Board

We, the undersigned residents and community members of Parma, Idaho off of Hwy 95 between Pearl and Grandview Roads, strongly oppose the proposed construction and operation of a slaughterhouse in or near our neighborhood.

We believe this project would negatively affect the health, safety, environment, and quality of life of local residents. Our concerns include, but are not limited to:

Odor and air pollution
Increased truck traffic and noise
Potential water and soil contamination
Negative impacts on nearby homes, schools, and businesses
Concerns regarding public health and sanitation
Decreased property values
Animal welfare concerns

Our neighborhood is not an appropriate location for an industrial slaughterhouse facility. We urge local officials and planning authorities to reject any rezoning requests, permits, or approvals associated with this project.

We respectfully request that decision-makers prioritize the well-being of residents and pursue alternative forms of economic development that are more compatible with our community.

By signing below, we express our opposition to the proposed slaughterhouse project in Parma, Idaho.

Name	Address	Signature	Date
Laura Carney	28114 Grandview Rd Parma ID		5/11/26
Jennifer McClain	28282 Grandview Rd. Parma ID		5/11/26

Name	Address	Signature	Date
Gary McClain	28282 Grandview Rd. Perris		5/11/26
Richard Hartshorn	28251 Grandview Rd		5/11/26
Sheila Hartshorn	28251 Grandview Rd	Sheila Hartshorn	5/11/2026